

路基土石方数量表

2026年印茶镇百城村洞巴屯龙瓜产业路项目-主线

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出											
	挖	填			I		II		III		IV		V		VI											土	土	石	土	石	土	石	土	石	
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	%	数量		土	土	石	土	石	土										
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34		
K0+000. 000	2. 05																																		
			1. 62	3					100	3											3								3		3		棱台法		
+001. 618	1. 51	0. 01	9. 22	17					100	17											17								17		17				
+010. 840	2. 13	0. 01	9. 16	17					100	17											17								17		17				
+020. 000	1. 56	0. 04	0. 06																																
+020. 061	1. 60	0. 04	15. 24	33					100	33											33								33		33				
+035. 301	2. 75	0. 02	4. 70	11					100	11											11								11		11				
+040. 000	1. 87	0. 09	20. 00	30					100	30							3	3			27								27		27				
+060. 000	1. 12	0. 20	10. 91	12					100	12							2	2			10								10		10				
+070. 908	1. 03	0. 22	9. 09	8					100	8							2	2			6								6		6				
+080. 000	0. 83	0. 26	20. 00	10					100	10							7	8			2								2		2				
+100. 000	0. 27	0. 41	6. 52	6					100	6							1	1			5								5		5				
+106. 515	1. 72	0. 07	13. 48	41					100	41											41								41		41				
+120. 000	4. 51		2. 57	13					100	13											13								13		13				
+122. 571	5. 59		15. 92	104					100	104											104								104		104				
+138. 491	7. 46		1. 51	10					100	10											10								10		10				
+140. 000	5. 50		14. 41	79					100	79											79								79		79				
+154. 411	5. 40		5. 59	22					100	22											22								22		22				
+160. 000	2. 76		20. 00	50					100	50											50								50		50				
+180. 000	2. 26		9. 88	21					100	21							2	2			19								19		19				
+189. 880	1. 93	0. 64	10. 12	14					100	14							8	9			5								5		5				
+200. 000	0. 98	0. 98	5. 21	9					100	9							4	4			5								5		5				
+205. 212	2. 74	0. 42	14. 79	49					100	49							2	2			47								47		47				
+220. 000	3. 91		0. 54	2					100	2											2								2		2				
+220. 543	3. 32		2. 63	9					100	9											9								9		9				
+223. 175	3. 36		9. 26	29					100	29											29								29		29				
+232. 435	2. 98		7. 56	25					100	25											25								25		25				
+240. 000	3. 66		1. 70	6					100	6											6								6		6				
+241. 696	3. 97																																		
小 计				630						630							31	33			597								597		597				

编制：

复核：

路基土石方数量表

SIII-2-24-2

2026年印茶镇百城村洞巴屯龙瓜产业路项目-主线

第 2 页 共 5 页

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出											
	挖	填			Ⅰ		Ⅱ		Ⅲ		Ⅳ		Ⅴ		Ⅵ											土	石								
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	土			石	土	石	土	石	土			石	土	石					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34		
+241.696	3.97																																		
			12.08	51					100	51											51								51		51				
+253.775	4.40		6.22	31					100	31											31								31		31				
+260.000	5.58		4.88	27					100	27											27								27		27				
+264.879	5.34		11.10	56					100	56											56								56		56				
+275.982	4.70		4.02	21					100	21											21								21		21				
+280.000	5.69		3.33	17					100	17											17								17		17				
+283.330	4.76		10.03	67					100	67											67								67		67				
+293.362	8.86	0.01	6.64	35					100	35							2	2			33								33		33				
+300.000	2.31	0.61	3.39	4					100	4							2	2			2								2		2				
+303.395	0.25	0.43	0.47																																
+303.861	0.23	0.14	6.51	3					100	3											3								3		3				
+310.375	0.83	0.01	6.51	3					100	3							1	1			2								2		2				
+316.889	0.17	0.36	3.11	1					100	1							1	1																	
+320.000	0.29	0.15	11.78	22					100	22							1	1			21								21		21				
+331.780	4.17		8.22	30					100	30											30								30		30				
+340.000	3.06		7.41	20					100	20											20								20		20				
+347.406	2.45	0.02	12.59	30					100	30											30								30		30				
+360.000	2.26	0.06	3.03	5					100	5											5								5		5				
+363.031	1.04	0.24	14.83	34					100	34							7	8			26								26		26				
+377.865	3.84	0.69	2.13	6					100	6							3	3			3								3		3				
+380.000	1.82	1.88	20.00	54					100	54							30	33			21								21		21				
+400.000	3.73	1.19	20.00	80					100	80							22	24			56				8				48		48				
+420.000	4.30	1.01	2.81	9					100	9							4	4			5				5										
+422.805	2.11	1.84	17.19	27					100	27							36	27		11			13												
+440.000	1.12	2.32	20.00	52					100	52							32	35			17								17		17				
+460.000	4.50	0.95	7.74	34					100	34							2	2			32								32		32				
+467.744	4.38		5.17	17					100	17											17								17		17				
+472.911	2.45	0.01																																	
小 计				736						736							143	143		11	593		13		13				580		580				

编制：

复核：

路基土石方数量表

SIII-2-24-3

2026年印茶镇百城村洞巴屯龙瓜产业路项目-主线

第 3 页 共 5 页

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出											
	挖	填			Ⅰ		Ⅱ		Ⅲ		Ⅳ		Ⅴ		Ⅵ											土	石	土	石	土	石	土	石		
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	%			数量	土	石	土	石	土									石	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34		
+472.911	2.45	0.01																																	
			7.09	24					100	24											24								24		24				
+480.000	4.48																																		
			12.26	55					100	55											55								55		55				
+492.260	4.56																																		
			7.74	33					100	33											33								33		33				
+500.000	3.94																																		
			11.61	34					100	34											34								34		34				
+511.610	1.95	0.08																																	
			8.39	17					100	17											17								17		17				
+520.000	2.19	0.01																																	
			7.66	14					100	14											14								14		14				
+527.660	1.56	0.13																																	
			12.34	37					100	37							1	1			36								36		36				
+540.000	4.67																																		
			9.39	39					100	39											39								39		39				
+549.392	3.75																																		
			10.61	43					100	43											43								43		43				
+560.000	4.27																																		
			11.12	54					100	54											54								54		54				
+571.123	5.41																																		
			8.78	51					100	51											51								51		51				
+579.905	6.24																																		
			0.10	1					100	1											1								1		1				
+580.000	6.28																																		
			11.66	63					100	63							3	3			60								60		60				
+591.658	4.50	0.90																																	
			8.34	27					100	27							7	8			19								19		19				
+600.000	2.12	0.86																																	
			3.41	6					100	6							2	2			4								4		4				
+603.411	1.66	0.31																																	
			4.35	7					100	7							1	1			6								6		6				
+607.765	1.50	0.09																																	
			12.02	13					100	13							3	3			10								10		10				
+619.784	0.71	0.39																																	
			0.22																																
+620.000	0.34	1.00																																	
			11.80	14					100	14							5	5			9								9		9				
+631.804	2.31	0.07																																	
			8.20	17					100	17											17								17		17				
+640.000	1.80	0.04																																	
			10.29	26					100	26											26								26		26				
+650.286	3.25																																		
			9.71	23					100	23											23								23		23				
+660.000	1.57	0.01																																	
			2.88	4					100	4											4								4		4				
+662.877	1.13	0.03																																	
			12.59	14					100	14							1	1			13								13		13				
+675.468	1.17	0.06																																	
			4.53	4					100	4							1	1			3								3		3				
+680.000	0.64	0.21																																	
			7.32	8					100	8							1	1			7								7		7				
+687.316	1.63	0.20																																	
			12.68	29					100	29							2	2			27								27		27				
+700.000	2.96	0.14																																	
				657						657							27	28			629								629		629				
小 计																																			

编制：

复核：

路基土石方数量表

2026年印茶镇百城村洞巴屯龙瓜产业路项目-主线

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出											
	挖	填			Ⅰ		Ⅱ		Ⅲ		Ⅳ		Ⅴ		Ⅵ											土	石								
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	土			石	土	石	土	石	土			石	土	石					
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34		
+700.000	2.96	0.14	1.23	4					100	4											4								4		4				
+701.226	2.84	0.15			13.91	33					100	33							1	1			32				5				27		27		
+715.136	1.97	0.04	2.94	5					100	5											5				5										
+718.077	1.75	0.17	1.92	4					100	4							1	1			3				3										
+720.000	1.91	0.45	20.00	25					100	25							26	25		3			3												
+740.000	0.69	2.46	10.95	15					100	15							23	15		9			9												
+750.949	2.18	1.72	9.05	17					100	17							17	17		1			1												
+760.000	1.58	1.99	20.00	37					100	37							24	26			11								11		11				
+780.000	2.12	0.54	3.82	8					100	8							2	2			6								6		6				
+783.822	2.09	0.55	16.18	42					100	42							3	3			39								39		39				
+800.000	3.13		5.56	23					100	23											23								23		23				
+805.564	5.10		14.44	73					100	73											73								73		73				
+820.000	5.01		12.03	71					100	71											71								71		71				
+832.031	6.79		7.97	38					100	38											38								38		38				
+840.000	2.93	0.01	18.50	81					100	81											81								81		81				
+858.497	6.05		1.50	4					100	4											4								4		4				
+860.000	0.65	0.12	12.86	18					100	18							1	1			17								17		17				
+872.855	2.39		7.14	9					100	9											9								9		9				
+880.000	0.44	0.04	10.54	6					100	6											6								6		6				
+890.544	0.69	0.02	9.46	15					100	15											15								15		15				
+900.000	2.74		8.23	33					100	33											33								33		33				
+908.232	5.52		11.77	65					100	65											65								65		65				
+920.000	5.49		11.67	40					100	40											40								40		40				
+931.673	1.72	0.03	8.33	17					100	17											17								17		17				
+940.000	2.39		20.00	61					100	61											61								61		61				
+960.000	3.71		3.31	6					100	6											6								6		6				
+963.312	0.48	0.20	16.69	40					100	40							1	1			39								39		39				
+980.000	5.10																																		
小 计				790						790							99	92		13	698		13		13				685		685				

编制：

复核：

路基土石方数量表

SIII-2-24-5

第 5 页 共 5 页

2026年印茶镇百城村洞巴屯龙瓜产业路项目-主线

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)												填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出									
	挖	填			Ⅰ		Ⅱ		Ⅲ		Ⅳ		Ⅴ		Ⅵ																		
					%	数量	%	数量	%	数量	%	数量	%	数量	%		数量	%		数量	土	土	石	土	石	土	石	土	石	土	石	土	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34
+980.000	5.10																																
+994.952	2.88		14.95	59					100	59											59								59		59		
K1+000.000	1.69	0.01	5.05	11					100	11											11								11		11		
+013.808	1.71		13.81	23					100	23											23								23		23		
+020.000	1.77		6.19	11					100	11											11								11		11		
+029.641	2.26		9.64	19					100	19											19								19		19		
+040.000	2.46		10.36	24					100	24											24								24		24		
+045.473	2.50		5.47	14					100	14											14								14		14		
+060.000	2.83		14.53	39					100	39											39								39		39		
+065.521	3.85		5.52	18					100	18											18								18		18		
+078.699	2.30		13.18	40					100	40											40								40		40		
+080.000	0.72	0.03	1.30	2					100	2											2								2		2		
+091.876	4.44		11.88	28					100	28											28								28		28		
+092.580	3.66		0.70	3					100	3											3								3		3		
+100.000	3.68		7.42	27					100	27											27								27		27		
+107.294	2.92		7.29	24					100	24											24								24		24		
+120.000	2.00		12.71	31					100	31											31								31		31		
+122.008	1.06		2.01	3					100	3											3								3		3		
+122.291	1.10		0.28																														
+131.638	1.27		9.35	11					100	11											11								11		11		
+140.000	1.17		8.36	10					100	10											10								10		10		
+140.985	1.28		0.98	1					100	1											1								1		1		
+160.000		0.14	19.02	8					100	8							1	1			7								7		7		
+180.000	1.13		20.00	8					100	8							1	1			7								7		7		
+190.000	1.30		10.00	12					100	12											12								12		12		
小 计				426					426								2	2			424								424		424		
合 计				3239					3239								302	298		24	2941			26		26			2915		2915		

编制：

复核: