

路基设计表

SIII-2-1-1

2026年印茶镇百城村洞巴屯龙瓜产业路项目-支线

第 1 页 共 2 页

桩号	平曲线		坡度及竖曲线		地面 高程 (m)	设计高程 PH (m)	填挖高度 (m)		路基宽度(m)		各点与设计高PH之高差(m)			边沟及排水沟						备注		
	左	右	凹	凸			填	挖	左 W1	右 W1	左 A1	中线 AB	右 B1	左			右					
														坡度	底宽	沟底高程	坡度	底宽	沟底高程			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21		
K0+000.000	R-10.000 Ly=-7.351		6.4514% 68.270		317.840	317.780		0.060	1.75	1.75	-0.035	0.000	-0.035								道路两侧排水沟间距1.5m	
ZY+003.876					318.000	318.030	0.030		1.75	2.04	0.006	0.000	-0.041									
QZ+010.366					318.400	318.449	0.049		1.75	2.50	0.070	0.000	-0.100									
YZ+016.855					318.750	318.868	0.118		1.75	1.90	0.014	0.000	-0.016									
ZY+019.301					319.000	319.025	0.025		1.75	1.75	-0.032	0.000	0.032									
+020.000					319.100	319.070		0.030	1.75	1.75	-0.050	0.000	0.050									
QZ+022.976					319.200	319.262	0.062		1.75	1.75	-0.129	0.000	0.129									
YZ+026.652					319.520	319.500		0.020	1.75	1.75	-0.017	0.000	0.017									
ZY+028.801					319.580	319.638	0.058		1.75	1.81	0.006	0.000	-0.006									
+040.000					320.250	320.361	0.111		1.75	2.35	0.053	0.000	-0.070									
QZ+047.027	R-80.000 Ly=-36.453				320.930	320.814		0.116	1.75	2.35	0.053	0.000	-0.070									
+060.000					321.920	321.651		0.269	1.75	2.16	0.024	0.000	-0.043									
YZ+065.254					322.100	321.990		0.110	1.75	1.84	-0.022	0.000	-0.037									
ZY+068.259					322.200	322.167		0.033	1.75	1.75	-0.009	0.000	-0.035									
QZ+079.039					322.450	322.487	0.037		1.75	1.75	0.140	0.000	-0.140									
+080.000	R-17.000 Ly=-21.561		2.863% 17.281		322.550	322.514		0.036	1.75	1.75	0.140	0.000	-0.140									
YZ+089.820					323.350	323.189		0.161	1.75	1.75	0.024	0.000	-0.024									
ZY+093.262					323.660	323.607		0.053	1.92	1.75	-0.017	0.000	0.015									
+100.000					324.600	324.426		0.174	2.60	1.75	-0.110	0.000	0.074									
QZ+101.754					324.850	324.639		0.211	2.75	1.75	-0.137	0.000	0.087									
YZ+110.246	R-40.000 Ly=-16.984		12.1512% 24.614		325.790	325.550		0.241	2.75	1.75	-0.137	0.000	0.087									
+120.000					326.140	325.904		0.236	1.77	1.75	-0.035	0.000	-0.032									
ZY+132.502					326.450	326.212		0.238	1.75	1.75	0.123	0.000	-0.123									
QZ+136.361					326.410	326.308		0.102	1.75	1.75	0.108	0.000	-0.108									
+140.000					326.450	326.397		0.053	1.75	1.75	0.059	0.000	-0.059									
YZ+140.219	R-22.000 Ly=-7.717		2.4689% 61.674		326.450	326.403		0.047	1.75	1.75	0.056	0.000	-0.056									
ZY+148.383					326.750	326.604		0.146	2.20	1.75	-0.060	0.000	0.048									
QZ+155.465					326.950	326.779		0.171	2.75	1.75	-0.165	0.000	0.105									
+160.000					327.050	326.891		0.159	2.47	1.75	-0.107	0.000	0.076									

编制：

复核：

路基设计表

SIII-2-1-2

2026年印茶镇百城村洞巴屯龙瓜产业路项目-支线

第 2 页 共 2 页

桩号	平曲线		坡度及竖曲线		地面 高程 (m)	设计高程 PH (m)	填挖高度		路基宽度(m)		各点与设计高PH之高差(m)			边沟及排水沟						备注
	左	右	凹	凸			(m)		左	右	左	中线	右	左			右			
							填	挖						W1	W1	A1	AB	B1	坡度	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
YZ+162.546	R-20.000 Ly-23.086	R-12.000 Ly-18.435	2.7240% 39.420	13.9411% 18.577	327.080	326.954		0.126	2.22	1.75	-0.062	0.000	0.049							
ZY+171.849								0.051	1.75	1.75	0.073	0.000	-0.073							
+180.000								0.079	1.75	1.75	0.158	0.000	-0.158							
QZ+181.066								0.130	1.75	1.75	0.158	0.000	-0.158							
YZ+190.284								0.265	1.75	1.75	0.040	0.000	-0.040							
ZY+195.387								0.393	1.75	1.75	-0.031	0.000	0.031							
+200.000								0.365	1.75	1.75	-0.088	0.000	0.088							
QZ+206.930								0.426	1.75	1.75	-0.123	0.000	0.123							
YZ+218.473								0.088		1.75	1.75	-0.071	0.000		0.071					
+220.000								0.080		1.75	1.75	-0.052	0.000		0.052					
ZY+230.069		R-100.000 Ly-17.599		11.4012% 17.795		0.041	1.75	2.01	0.030	0.000	-0.035									
QZ+238.868						0.381	1.75	2.20	0.053	0.000	-0.066									
+240.000						0.691	1.75	2.20	0.053	0.000	-0.066									
YZ+247.668						0.150	1.75	2.20	0.053	0.000	-0.066									
+260.000					6.2273% 48.541		0.150	1.75	1.75	-0.035	0.000	-0.035								
+280.000							0.104	1.75	1.75	-0.035	0.000	-0.035								
ZY+291.201							0.219	1.75	1.75	-0.158	0.000	0.158								
QZ+295.895							0.264	1.75	1.75	-0.158	0.000	0.158								
+300.000							0.138	1.75	1.75	-0.158	0.000	0.158								
YZ+300.590					R-12.000 Ly-9.389	3.0614% 18.828		0.120	1.75	1.75	-0.146	0.000	0.146							
+310.000		0.022	1.75	1.75			-0.035	0.000	-0.035											

编制：

复核：