

路基土石方数量表

2026年印茶镇百城村洞巴屯龙瓜产业路项目-支线

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)								借方数量		弃方数量		总 运 量		备 注	
	(平方米)			总数量	土						石						本桩利用		填缺	挖余		调入		调出										
	挖	填			I		II		III		IV		V		VI											土	土	石	土	石	土	石		土
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量	%	数量		土	土	石	土	石	土								石	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	
K0+000. 000	1. 08																																	
			3. 88	4					100	4												4							4		4		棱台法	
+003. 876	0. 83		6. 49	6					100	6												6							6		6			
+010. 366	1. 10	0. 01	6. 49	5					100	5												5							5		5			
+016. 855	0. 42	0. 01	2. 45	1					100	1												1							1		1			
+019. 301	0. 72		0. 70	1					100	1												1							1		1			
+020. 000	0. 91		2. 98	2					100	2												2							2		2			
+022. 976	0. 59	0. 01	3. 68	3					100	3												3							3		3			
+026. 652	0. 88		2. 15	2					100	2												2							2		2			
+028. 801	0. 61		11. 20	7					100	7												7							7		7			
+040. 000	0. 69	0. 01	7. 03	8					100	8												8							8		8			
+047. 027	1. 65		12. 97	24					100	24												24							24		24			
+060. 000	2. 10		5. 25	9					100	9												9							9		9			
+065. 254	1. 29		3. 00	3					100	3												3							3		3			
+068. 259	0. 96		10. 78	9					100	9												9							9		9			
+079. 039	0. 68	0. 02	0. 96	1					100	1												1							1		1			
+080. 000	0. 94	0. 01	9. 82	11					100	11												11							11		11			
+089. 820	1. 37		3. 44	4					100	4												4							4		4			
+093. 262	1. 03	0. 01	6. 74	9					100	9							1	1				8							8		8			
+100. 000	1. 54	0. 22	1. 75	3					100	3												3							3		3			
+101. 754	1. 69	0. 31	8. 49	15					100	15							2	2				13							13		13			
+110. 246	1. 82	0. 27	9. 75	17					100	17							1	1				16							16		16			
+120. 000	1. 72		12. 50	21					100	21												21							21		21			
+132. 502	1. 66		3. 86	5					100	5												5							5		5			
+136. 361	1. 17		3. 64	4					100	4												4							4		4			
+140. 000	0. 99		0. 22																															
+140. 219	0. 97		8. 16	10					100	10												10							10		10			
+148. 383	1. 41	0. 03	7. 08	10					100	10							1	1				9							9		9			
+155. 465	1. 54	0. 32															5	5				189							189		189			
小 计				194						194							5	5				189							189		189			

编制：

复核：

路基土石方数量表

2026年印茶镇百城村洞巴屯龙瓜产业路项目-支线

起讫桩号	横断面面积		距离 (米)	挖方分类及数量(立方米)														填方 数量 立方米	利用方数量及调配(立方米)										借方数量		弃方数量		总 运 量		备 注
	(平方米)			总数量	土						石								本桩利用		填缺	挖余		调入		调出									
	挖	填			Ⅰ		Ⅱ		Ⅲ		Ⅳ		Ⅴ		Ⅵ		土											土	石	土	石	土	石	土	
					%	数量	%	数量	%	数量	%	数量	%	数量	%	数量			%	数量		土	石	土	石	土	石								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34		
+155.465	1.54	0.32																																	
			4.53	7					100	7							1	1			6								6		6				
+160.000	1.47	0.13																			4								4		4				
+162.546	1.33	0.04							100	4											11								11		11				
+171.849	0.99								100	11											8								8		8				
+180.000	1.09								100	8											1								1		1				
+181.066	1.28								100	1											14								14		14				
+190.284	1.75								100	14											10								10		10				
+195.387	2.22								100	10											10								10		10				
+200.000	2.12								100	10											15								15		15				
+206.930	2.35								100	15											15								15		15				
+218.473	0.50								100	15											15								15		15				
+220.000	0.53								100	1											1								1		1				
+230.069	1.12								100	1											8								8		8				
+238.868	2.85								100	8											17								17		17				
+240.000	4.27								100	17											4								4		4				
+247.668	2.04								100	4											24								24		24				
+260.000	1.40								100	24											21								21		21				
+280.000	1.24								100	21											26								26		26				
+291.201	1.59								100	26											16								16		16				
+295.895	1.75								100	16											8								8		8				
+300.000	1.30								100	8											6								6		6				
+300.590	1.23								100	6											1								1		1				
+310.000	0.94								100	1											10								10		10				
小 计				237						237							1	1			236								236		236				
合 计				431						431							6	6			425								425		425				

编制：

复核：