

路基防护工程数量表
(挡土墙)

序号	桩 号/路线	位置	结构形式 及主要尺寸	平均高度	长 度	拆除旧墙	工 程 项 目 及 数 量									备 注
							C20片石混凝土			M7.5浆砌片石		挖 基				
								墙 身	基 础	墙 身	基 础	普土	硬土	软石	次坚石	
				(m)	(m)	(m3)	(m³)				(m³)					
1	k0+00-k0+060A线HQ一	左侧	重力式路肩墙	3	20			67.4	24.4				29.28	14.64		
2	k0+405-k0+430A线HQ二	右侧	重力式锁脚墙	2	23			46	23.23				27.876	13.938		
3	K0+005-K0+030B线HQ三	左侧	重力式锁脚墙	3	24			80.88	29.28				35.136	17.568		
4	K0+005-K0+030B线HQ三	右侧	重力式锁脚墙	3	20			67.4	24.4				29.28	14.64		
5																
合 计								261.68	101.31				121.57	60.79		

编制：蒙昌鼎

复核：王跃文