

K0+014.5勒德桥公路施工图预算

()

第 册 共 册

编制:

吴明兰

复核:

陈华生

(西林县财政投资评审中心)

二零二五年八月

表A.0.2-5 总预算表

建设项目名称：西林县古障镇央草村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

01表

第 1 页 共 3 页

子项编号	工程或费用名称	单位	数量	金额（元）	技术经济指标	各项费用比例(%)	备注
1	第一部分 建筑安装工程费	桥长米	23.04	652046.69	28300.64	100.00	建设项目路线总长度（主线长度）
101	临时工程	桥长米	23.04	25414.03	1103.04	3.90	
10101	临时道路	m	60	8084.78	134.75	1.24	
1010101	临时便道（修建、拆除与维护）	m	60	8084.78	134.75	1.24	
101010101	路基土石方工程	m3	270	3698.73	13.7	0.57	
101010102	8cm泥结碎石面层	m2	210	4386.05	20.89	0.67	
101010103	临时便桥、便涵	m	8	4966.21	620.78	0.76	
101010104	临时涵洞	m	8	4966.21	620.78	0.76	
101010105	临时供电设施	总额	1	12363.04	12363.04	1.90	
102	路基工程	元		1409.46		0.22	
LJ01	场地清理	元					
LJ03	路基填方	m3	99	1409.46	14.24	0.22	
LJ0302	借土方填筑	m3	99	1409.46	14.24	0.22	
103	路面工程	元		27185.74		4.17	
LM02	水泥混凝土路面	m2	205	27185.74	132.61	4.17	
LM0203	路面基层	m2	227	5329.64	23.48	0.82	
LM020304	级配碎石基层 厚8cm	m2	227	5329.64	23.48	0.82	
LM0205	水泥混凝土面层	m2	205	21856.1	106.62	3.35	
LM020501	水泥混凝土 厚18cm	m2	205	21856.1	106.62	3.35	
104	桥梁涵洞工程	桥长米	23.04	588401.3	25538.25	90.24	
10401	小桥工程	m/座	23.04 / 1	588401.3	25538.25 / 588401.3	90.24	
1040102	勒德桥	m2/m	126.72 / 23.04	588401.3	4643.32 / 25538.25	90.24	
QL01	基础工程	m3	183	130350.98	712.3	19.99	
QL0101	扩大基础	m3	183	109322.02	597.39	16.77	

编制：吴明兰（西林县财政投资评审中心）

复核：陈华生

表A.0.2-5 总预算表

建设项目名称: 西林县古障镇央草村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围: K0+014.5勒德桥

01表

第 2 页 共 3 页

子项编号	工程或费用名称	单位	数量	金额 (元)	技术经济指标	各项费用比例 (%)	备注
QL01C101	现浇C25混凝土基础	m3	183	109322.02	597.39	16.77	
QL01C7	挖基坑	m3	585	21028.96	35.95	3.23	
QL01C701	挖土方	m3	468	9976.17	21.32	1.53	
QL01C702	挖石方	m3	117	6752.81	57.72	1.04	
QL01C703	弃土方	m3	468	3246.38	6.94	0.50	
QL01C704	弃石方	m3	117	1053.6	9.01	0.16	
QL02	下部构造			201894.36		30.96	
QL02C1	现浇C30砼台身	m3	210.8	171385.17	813.02	26.28	
QL02C2	现浇C30砼台帽及侧墙	m3	10.42	20834.44	1999.47	3.20	
QL02C3	现浇C30砼挡块及支座垫石	m3	0.5	1852.12	3704.24	0.28	
QL02C4	台背回填	m3	135	7822.63	57.95	1.20	
QL03	上部构造	m3	30.4	73503.94	2417.89	11.27	
QL03C1	现浇钢筋混凝土矩形板	m3	30.4	73503.94	2417.89	11.27	
QL04	桥面铺装	m3	11.9	22823.78	1917.96	3.50	
QL04C2	现浇C40防水混凝土铺装	m3	11.9	20460.84	1719.4	3.14	
QL04C4	桥面连续	t	0.431	2362.94	5482.46	0.36	
QL05	桥梁附属结构			110386.95		16.93	
QL05C1	桥梁支座	个	10	2026.34	202.63	0.31	
QL05C104	板式橡胶支座	dm3	11.618	2026.34	174.41	0.31	
QL05C2	伸缩缝	m	5.5	18734.68	3406.31	2.87	
QL05C202	沥青麻絮伸缩缝	m	5.5	18734.68	3406.31	2.87	
QL05C3	护栏与护网	m	46.08	33530.75	727.66	5.14	
QL05C304	现浇C30混凝土防撞护栏	m	46.08	33530.75	727.66	5.14	
QL05C4	现浇C30砼搭板枕梁	m3	15.8	22719.24	1437.93	3.48	
QL05C5	锥坡排水及防护	m3	50.5	23348.67	462.35	3.58	

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.2-5 总预算表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

01表

第 3 页 共 3 页

分项编号	工程或费用名称	单位	数量	金额（元）	技术经济指标	各项费用比例（%）	备注
QL0506	台后排水	m3	32.4	6862.43	211.8	1.05	
QL0507	泄水管	套	18	3164.81	175.82	0.49	
QL06	其他工程	桥长米	23.04	49441.23	2145.89	7.58	
QL0601	满堂木支架	m2	97.5	17642.33	180.95	2.71	
QL0602	编织袋围堰（高1.5m）	m	42	11652.87	277.45	1.79	
QL0603	M7.5浆砌片石挡墙	m3	46.2	20146.05	436.06	3.09	
110	专项费用	元		9636.13		1.48	
11002	安全生产费	元		9636.13		1.48	
2	第二部分 土地使用及拆迁补偿费	桥长米	23.04				
3	第三部分 工程建设其他费	桥长米	23.04				
4	第四部分 预备费	桥长米					
401	基本预备费	元					
402	价差预备费	元					
5	第一至四部分合计	桥长米	23.04	652046.63	28300.64	100.00	
6	建设期贷款利息	桥长米					
7	公路基本造价	桥长米	23.04	652046.63	28300.64	100.00	

编制：吴明兰（西林县财政投资评审中心）

复核：陈华生

表A.0.2-6 人工、主要材料、施工机械台班数量汇总表

建设项目名称: 西林县古障镇央革村勒德屯司入平沙糖桔产业桥梁建设项目
编制范围: K0+014.5勒德桥

代号	规格名称	单位	单价 (元)	总数量	分项统计							场外运输损耗		
					临时工程	路基工程	路面工程	桥梁涵洞工程					辅助生产	%
1001001	人工	工日	101.25	991.488	31.251	0.515	35.329	924.394						
1051001	机械工	工日	101.25	75.661	0.147	1.635	2.498	71.38						
2001001	HPB300钢筋	t	3708.93	0.666			0.001	0.665						
2001002	HRB400钢筋	t	3726.76	18.628				18.628						
2001019	钢丝绳 (股丝6-7×19, 绳径7.1~9mm; 股丝6×37, 绳径14.1~15.5mm)	t	6000	0.053				0.053						
2001020	钢纤维 (扁丝切断型、钢丝切断型、高强度销型、剪切波纹型、剪切压痕型)	t	6000	0.003				0.003						
2001021	8~12号铁丝 (镀锌铁丝)	kg	5.28	22.972	4.2			18.772						
2001022	20~22号铁丝 (镀锌铁丝)	kg	5.57	51.38				51.38						
2003004	型钢 (工字钢, 角钢)	t	3783.18	0.043	0.015		0.01	0.018						
2003005	钢板 (Q235, δ=5~40mm)	t	5720	0.178	0.05			0.128						
2003008	钢管 (无缝钢管)	t	4301.22	0.199				0.199						
2003025	钢模板 (各类定型大块钢模板)	t	5247.26	1.858				1.858						
2003026	组合钢模板	t	4766.68	0.005				0.005						
2009003	空心钢杆 (优质碳素工具钢)	kg	8.5	1.615				1.615						
2009004	Φ50mm以内合金钻头 (Φ43mm)	个	35	2.457				2.457						
2009011	电焊条 (结422(502、506、507)E2 /4.0/5.0)	kg	6.64	31.069				31.069						
2009013	螺栓 (混合规格)	kg	5.64	118.802				118.802						
2009028	铁件 (铁件)	kg	5.65	235.865	11.5			224.365						
2009030	铁钉 (混合规格)	kg	5.65	4.778				4.778						
2009033	铸铁管	kg	3.42	725.4				725.4						

编制: 吴明兰 (西林县财政投资评审中心)

复核: 陈华生

表A.0.2-6 人工、主要材料、施工机械台班数量汇总表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：KO+014.5勒德桥

代号	规格名称	单位	单价 (元)	总数量	分项统计						场外运输损耗	
					临时工程	路基工程	路面工程	桥梁涵洞工程			辅助生产	% 数量
3001001	石油沥青	t	4451.04	0.019			0.019					
3003002	汽油 (92号)	kg	8.98	8.592				8.592				
3003003	柴油 (0号, -10号, -20号)	kg	7.3	1272.936	7.694	73.301	27.632	1164.308				
3005001	煤	t	561.95	0.004			0.004					
3005002	电	kW·h	0.73	2364.646			70.941	2293.705				
3005004	水	m3	3.84	674.369	4.41		5.535	664.424				
4003001	原木 (混合规格)	m3	389.57	4.999				4.999				
4003002	锯材 (中板 δ = 19~35mm, 中方混合规格)	m3	1047.93	1.199			0.014	1.185				
5001013	PVC塑料管 (Φ50mm) (Φ50mm)	m	9.73	8.316				8.316				
5001052	塑料编织袋 (袋装砂井用)	个	1.2	2280.6				2280.6				
5005002	硝酸炸药 (1号、2号岩石硝酸炸药)	kg	12	18.381				18.381				
5005008	非电毫秒雷管 (导爆管长3~7m)	个	15.9	23.517				23.517				
5005009	导爆索 (爆速6000~7000m/s)	m	2.05	10.624				10.624				
5007001	土工布 (宽4~5m)	m2	5.6	24.17				24.17				
5009005	桥面防水涂料 (聚合物渗透水性桥面防水涂料)	kg	15.04	210.163				210.163				
5009012	油毛毡 (400g, 0.915m×21.95m)	m2	3.5	21.28				21.28				
5501003	黏土 (堆方)	m3	28	19.823	4.801			15.023				
5501005	碎石土 (天然堆方)	m3	32.04	165.24				165.24				
5503004	砂 (路面用堆方)	m3	160	12.113				12.113				
5503005	中 (粗) 砂 (混凝土、砂浆用堆方)	m3	150	285.486			17.313	268.173				
5505005	片石 (码方)	m3	135	104.557				104.557				
5505012	碎石 (2cm) ★ 最大粒径2cm堆方)	m3	145	319.996				319.996				

编制：吴明兰 (西林县财政投资评审中心)

复核：陈华生

表A.0.2-6 人工、主要材料、施工机械台班数量汇总表

建设项目名称：西林县古障镇央草村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

代号	规格名称	单位	单价 (元)	总数量	分项统计						场外运输损耗		
					临时工程	路基工程	路面工程	桥梁涵洞工程				辅助生产	%
5505013	碎石（4cm）（最大粒径4cm堆方）	m3	145	106.609			31.616	74.993					
5505015	碎石（8cm）（最大粒径8cm堆方）	m3	145	15.833				15.833					
5505016	碎石（未筛分碎石统料堆方）	m3	145	48.632	20.788		27.844						
5509001	32.5级水泥	t	430	69.105				69.105					
5509002	42.5级水泥	t	450	139.975			13.361	126.614					
5511002	钢筋混凝土电杆(7m)	根	264.1	3	3								
6001002	四氟板式橡胶组合支座（GJZF4系列、GYZF4系列）	dm3	59.83	11.618				11.618					
6003004	模数式伸缩装置240型	m	2393.16	5.5				5.5					
7001009	120/20 聚乙烯绝缘电力电缆（规格120/20）	m	14.02	315	315								
7801001	其他材料费	元	1	3065.732	157.8		52.767	2855.165					
7901001	设备摊销费	元	1	3698.377	3697.9		0.477						
8001002	功率75kW以内履带式推土机（TY100）	台班	866.45	0.149				0.149					
8001027	斗容量1.0m3履带式单斗挖掘机（WY100液压）	台班	1174.46	0.196		0.196							
8001030	斗容量2.0m3履带式单斗挖掘机（WY200A液压）	台班	1478.3	0.149				0.149					
8001035	斗容量1.0m3履带式单斗挖掘机（WK100机械）	台班	1033.08	1.65				1.65					
8001045	斗容量1.0m3轮胎式装载机（ZL20）	台班	573.85	0.828				0.828					
8001058	功率120kW以内平地机（F155）	台班	1168.27	0.308		0.146		0.162					
8001066	功率75kW以内履带式拖拉机	台班	642.26	0.05			0.05						
8001080	机械自身质量10~12t光轮压路机（3Y-10/12）	台班	503	0.277		0.277							
8001081	机械自身质量12~15t光轮压路机（3Y-12/15）	台班	576.46	0.377	0.056		0.027	0.297					

编制：吴明兰 (西林县财政投资评审中心)

复核：陈华生

表A.0.2-6 人工、主要材料、施工机械台班数量汇总表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目

编制范围: K0+014.5勒德桥

代号	规格名称	单位	单价 (元)	总数量	分项统计						场外运输损耗		
					临时工程	路基工程	路面工程	桥梁涵洞工程			辅助生产	%	数量
8001083	机械自身质量18~21t光轮压路机 (3Y-18/21)	台班	739.61	0.276	0.095		0.182						
8001095	蛙式夯土机(200~620N·m)(HW-280)	台班	27.8	0.459				0.459					
8003038	容量4000L以内沥青洒布车(LS-3500)	台班	606.84	0.008				0.008					
8003079	混凝土电动真空吸水机组(含吸垫5m×5m)	台班	134.92	0.506			0.506						
8003085	电动混凝土切缝机(含锯片摊销费用)(SLF)	台班	202.97	1.402			0.51	0.893					
8005002	出料容量250L以内强制式混凝土搅拌机(JD250)	台班	166.33	1.521			0.976	0.545					
8005005	出料容量750L以内强制式混凝土搅拌机(JS750)	台班	318.92	9.442				9.442					
8005010	出料容量400L以内灰浆搅拌机(UJ325)	台班	130.18	1.308				1.308					
8007014	装载质量8t以内自卸汽车(QD351)	台班	668.83	5.114				5.114					
8007015	装载质量10t以内自卸汽车(QD361)	台班	747.22	0.675		0.675							
8007041	容量6000L以内洒水汽车(YGJ5102GSSEQ)	台班	717.03	0.243				0.243					
8007043	容量10000L以内洒水汽车(YGJ5170GSSJN)	台班	1093.21	0.248			0.248						
8007046	装载质量1.0t以内机动翻斗车(F10A)	台班	206.5	15.654				15.654					
8009027	提升质量12t以内汽车式起重机(QY12)	台班	835.14	0.94				0.94					
8009030	提升质量25t以内汽车式起重机(QY25)	台班	1342.51	12.252				12.252					
8015013	锯片直径500mm以内木工圆锯机(MJ-106)	台班	125.76	0.78				0.78					
	-					-					-		

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.2-7 建筑安装工程费计算表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

序号	分项编号	工程名称	单位	工程量	定额直接费(元)	定额设备购置费(元)	直接费(元)				设备购置费	措施费	企业管理费	规费	利润(元)		税金(元)	金额合计(元)	
							人工费	材料费	施工机械使用费	合计					费率(%)	税率(%)		合计	单价
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	
1	I01	临时工程	桥长米	23.04	18671.58		3164.16	16261.24	740.16	20165.56		179.13	472.2	1064.98	1433.76	2098.41	25414.03	1103.04	
2	I0101	临时道路	m	60	4587.26		2708.54	3165.6	100.16	5974.29		57.94	119.14	912.35	353.51	667.55	8084.78	134.75	
3	I010101	临时便道(修建、拆除与维护)	m	60	4587.26		2708.54	3165.6	100.16	5974.29		57.94	119.14	912.35	353.51	667.55	8084.78	134.75	
4	I01010101	路基土石方工程	m3	270	2439.13		2323.69			2323.69		35.61	67	778.44	188.6	305.4	3698.73	13.7	
5	I0101010101	8cm泥结碎石面层	m2	210	2148.13		384.85	3165.6	100.16	3650.61		22.33	52.14	133.91	164.92	362.15	4386.05	20.89	
6	I0102	临时便桥、便涵	m	8	4241.44			3601.44	640	4241.44					314.72	410.05	4966.21	620.78	
7	I010202	临时涵洞	m	8	4241.44			3601.44	640	4241.44					314.72	410.05	4966.21	620.78	
8	I0104	临时供电设施	总额	1	9842.88		455.63	9494.2		9949.82		121.19	353.06	152.63	765.53	1020.8	12363.04	12363.04	
9	I02	路基工程	元		1116.68		52.12		1044.18	1096.3		14.53	23.64	72.93	85.69	116.38	1409.46		
10	IJ03	路基填方	m3	99	1116.68		52.12		1044.18	1096.3		14.53	23.64	72.93	85.69	116.38	1409.46	14.24	
11	IJ0302	借土方填筑	m3	99	1116.68		52.12		1044.18	1096.3		14.53	23.64	72.93	85.69	116.38	1409.46	14.24	
12	I03	路面工程	元		16090.52		3577.01	17446.27	833.36	21856.63		174.98	390.52	1283.04	1235.88	2244.69	27185.74		
13	LM02	水泥混凝土路面	m2	205	16090.52		3577.01	17446.27	833.36	21856.63		174.98	390.52	1283.04	1235.88	2244.69	27185.74	132.61	
14	LM0203	路面基层	m2	227	2592.03		264.31	4037.83	201.94	4504.09		25.74	62.91	97.94	198.91	440.06	5329.64	23.48	
15	LM020304	级配碎石基层 厚8cm	m2	227	2592.03		264.31	4037.83	201.94	4504.09		25.74	62.91	97.94	198.91	440.06	5329.64	23.48	
16	LM0205	水泥混凝土面层 厚18cm	m2	205	13498.49		3312.7	13408.44	631.41	17352.55		149.24	327.61	1185.1	1036.97	1804.63	21156.1	106.62	
17	LM020501	水泥混凝土面层 厚18cm	m2	205	13498.49		3312.7	13408.44	631.41	17352.55		149.24	327.61	1185.1	1036.97	1804.63	21156.1	106.62	
18	I04	桥梁涵洞工程	桥长米	23.04	384314.97		93594.86	328804.99	32954.05	455353.9		5580.08	15060.61	33775.41	30047.71	48583.59	588401.3	25538.25	
19	I0402	小桥工程	m/座	23.04	384314.97		93594.86	328804.99	32954.05	455353.9		5580.08	15060.61	33775.41	30047.71	48583.59	588401.3	25538.25	
20	I040202	勒德桥	m2/m	126.72	384314.97		93594.86	328804.99	32954.05	455353.9		5580.08	15060.61	33775.41	30047.71	48583.59	588401.3	4643.32	

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.2-7 建筑安装工程费计算表

建设项目名称: 西林县古障镇央草村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围: K0+014.5勒德桥

第 2 页共 3 页

03表

序号	分项编号	工程名称	单位	工程量	定额直接费(元)	定额设备购置费(元)	直接费(元)				设备购置费	措施费	企业管理费	规费	利润(元)		税金(元)	金额合计(元)	
							人工费	材料费	施工机械使用费	合计					费率(%)	税率(%)		合计	单价
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	
21	QL01	基础工程	m3	1837	3269.02		20113.69	68517.03	12411.62	101042.33		1344.42	3418.84	7547.27	6235.2	10762.93	130350.98	712.3	
22	QL0101	扩大基础	m3	183	64585.92		12080.75	67798.47	6665.07	86544.29		1109	2975.91	4570.86	5095.38	9026.59	109322.02	597.39	
23	QL010101	现浇C25混凝土基础	m3	183	64585.92		12080.75	67798.47	6665.07	86544.29		1109	2975.91	4570.86	5095.38	9026.59	109322.02	597.39	
24	QL0107	挖基坑	m3	585	14683.1		8032.94	718.56	5746.54	14498.04		235.42	442.93	2976.41	1139.82	1736.34	21028.96	35.95	
25	QL010701	挖土方	m3	468	5791.09		5221.83		1286.06	6507.89		99.15	186.55	1833.76	525.1	823.72	9976.17	21.32	
26	QL010702	挖石方	m3	117	4413.52		2811.12	718.56	1040.04	4569.71		97.56	208.58	969.19	350.2	557.57	6752.81	57.72	
27	QL010703	弃土方	m3	468	2626.18				2582.35	2582.35		29.23	36.08	130.96	199.71	268.05	3246.38	6.94	
28	QL010704	弃石方	m3	117	852.31				838.09	838.09		9.49	11.71	42.5	64.82	87	1053.6	9.01	
29	QL02	下部构造			131962.42		30833.67	109319.08	15475.41	155628.16		2143.04	5700.78	11378.57	10373.62	16670.18	201894.36		
30	QL0201	现浇C30砼台身	m3	210.8	110018.02		27529.47	90679.01	13249.81	131458.3		1934.16	5032.24	10129.16	8680.24	14151.07	171385.17	813.02	
31	QL0202	现浇C30砼台帽及侧墙	m3	10.42	14337.2		2878.06	12246.2	1219.96	16344.22		152.96	456.6	1051.33	1109.05	1720.28	20834.44	1999.47	
32	QL0203	现浇C30砼挡块及支座垫石	m3	0.5	1302.86		248.45	1099.57	109.98	1458		12.83	38.76	89.11	100.5	152.93	1852.12	3704.24	
33	QL0204	台背回填	m3	135	5304.34		177.69	5294.29	895.66	6367.65		43.09	173.18	108.98	483.83	645.91	7822.63	57.95	
34	QL03	上部构造	m3	30.4	51103.56		7803.39	48455.95	2380.18	58639.52		434.39	1550.52	2806.77	3943.62	6069.13	73503.94	2417.89	
35	QL0301	现浇钢筋混凝土矩形板	m3	30.4	51103.56		7803.39	48455.95	2380.18	58639.52		434.39	1550.52	2806.77	3943.62	6069.13	73503.94	2417.89	
36	QL04	桥面铺装	m3	11.9	15123.57		2861.83	14568.94	723.75	18154.52		143.2	406.2	1072.41	1162.93	1884.53	22823.78	1917.96	
37	QL0402	现浇C40防水混凝土铺装	m3	11.9	13412.89		2643.64	12909.01	691.04	16243.68		133.55	367.84	993.9	1032.44	1689.43	20460.84	1719.4	
38	QL0404	桥面连续	t	0.431	1710.68		218.19	1659.93	32.71	1910.84		9.65	38.35	78.5	130.49	195.11	2362.94	5482.46	
39	QL05	桥梁附属结构			73218.03		17169.3	67605.51	1494.07	86268.88		859.87	2517.86	5942.42	5683.4	9114.52	110386.95		
40	QL0501	桥梁支座	个	10	1391.61		117.63	1507.33	41.57	1666.53		7.85	31.2	47.29	106.16	167.31	2026.34	202.63	
41	QL050104	板式橡胶支座	dm3	11.618	1391.61		117.63	1507.33	41.57	1666.53		7.85	31.2	47.29	106.16	167.31	2026.34	174.41	

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.2-8 综合费率计算表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围: KO+014 5勒德桥

序号	工程类别	措施费 (%)										企业管理费 (%)								规费 (%)					
		冬季 施工 增加 费	雨季 施工 增加 费	夜间 施工 增加 费	高原 地区 施工 增加 费	风沙 地区 施工 增加 费	沿海 地区 施工 增加 费	行车 干扰 施工 增加 费	施工 辅助 费	工地 转移 费	综合费率		基本 费用	主副 食运 费补 贴	职工 探亲 路费	职工 取暖 补贴	财务 费用	综合 费率	养老 保险 费	失业 保险 费	医疗 保险 费	工伤 保险 费	住房 公积 金	综合 费率	
											I	II													
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
01	土方		0.939						0.521		0.939	0.521	2.747						2.747	16	0.5	7.5	1	8.5	33.5
02	石方		0.876						0.47		0.876	0.47	2.792						2.792	16	0.5	7.5	1	8.5	33.5
03	运输		0.959						0.154		0.959	0.154	1.374						1.374	16	0.5	7.5	1	8.5	33.5
04	路面		0.94						0.818		0.94	0.818	2.427						2.427	16	0.5	7.5	1	8.5	33.5
05	隧道								1.195			1.195	3.569						3.569	16	0.5	7.5	1	8.5	33.5
06	构造物 I		0.622						1.201		0.622	1.201	3.587						3.587	16	0.5	7.5	1	8.5	33.5
06-1	构造物 I (绿化)		0.622						1.201		0.622	1.201	3.587						3.587	16	0.5	7.5	1	8.5	33.5
07	构造物 II		0.742						1.537		0.742	1.537	4.726						4.726	16	0.5	7.5	1	8.5	33.5
08	构造物 III (一般)		1.497						2.729		1.497	2.729	5.976						5.976	16	0.5	7.5	1	8.5	33.5
08-1	构造物 III (室内)								2.729			2.729	5.976						5.976	16	0.5	7.5	1	8.5	33.5
08-2	构造物 III (桥梁)		1.497						2.729		1.497	2.729	5.976						5.976	16	0.5	7.5	1	8.5	33.5
08-3	构造物 III (设备安装)								2.729			2.729	5.976						5.976	16	0.5	7.5	1	8.5	33.5
09	技术复杂大桥		0.907						1.677		0.907	1.677	4.143						4.143	16	0.5	7.5	1	8.5	33.5
10	钢材及钢铰拱 (一般)								0.564			0.564	2.242						2.242	16	0.5	7.5	1	8.5	33.5
10-1	钢材及钢铰拱 (桥梁)								0.564			0.564	2.242						2.242	16	0.5	7.5	1	8.5	33.5
10-2	钢材及钢铰拱 (金属标志牌等)								0.564			0.564	2.242						2.242	16	0.5	7.5	1	8.5	33.5

编制: 吴明兰 (西林县财政投资评审中心)

复核: 陈华生

表A.0.2-9 综合费计算表

建设项目名称: 西林县古障镇央草村勒德屯司入平沙糖桔产业桥梁建设项目
编制范围: K0+01~+5勒德桥

序号	工程名称	措施费										企业管理费							规费						
		冬季 施工 增加 费	雨季 施工 增加 费	夜间 施工 增加 费	高原 地区 施工 增加 费	风沙 地区 施工 增加 费	沿海 地区 施工 增加 费	行车 干扰 施工 增加 费	施工 辅助 费	工地 转移 费	综合费用		基本 费用	主副 食运 费补 贴	职工 探亲 路费	职工 取暖 补贴	财务 费用	综合 费用	养老 保险 费	失业 保险 费	医疗 保险 费	工伤 保险 费	住房 公积 金	综合 费用	
											I	II													
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
1	路基土石方工程		22.9						12.71		22.9	12.71	67						67	371.79	11.62	174.28	23.24	197.51	778.44
2	8cm泥结碎石面层		4.76						17.57		4.76	17.57	52.14						52.14	63.96	2	29.98	4	33.98	133.91
3	临时涵洞																								
4	临时供电设施		2.98						118.21		2.98	118.21	353.06						353.06	72.9	2.28	34.17	4.56	38.73	152.63
5	借土方填筑		10.59						3.94		10.59	3.94	23.64						23.64	34.84	1.09	16.33	2.18	18.51	72.93
6	级配碎石基层 厚8cm		4.54						21.2		4.54	21.2	62.91						62.91	46.78	1.46	21.93	2.92	24.85	97.94
7	水泥混凝土 厚18cm		38.82						110.42		38.82	110.42	327.61						327.61	566.02	17.69	265.32	35.38	300.71	1185.1
8	现浇C25混凝土基础		143.46						965.54		143.46	965.54	2975.91						2975.91	2183.1	68.22	1023.33	136.44	1159.77	4570.86
9	挖土方		63.77						35.38		63.77	35.38	186.55						186.55	875.83	27.37	410.54	54.74	465.28	1833.76
10	挖石方		29.72						67.84		29.72	67.84	208.58						208.58	462.98	14.47	216.98	28.93	245.91	969.19
11	弃土方		25.19						4.04		25.19	4.04	36.08						36.08	62.55	1.96	29.32	3.91	33.23	130.96
12	弃石方		8.17						1.31		8.17	1.31	11.71						11.71	20.3	0.63	9.52	1.27	10.78	42.5
13	现浇C30砼台身		305.47						1628.69		305.47	1628.69	5032.24						5032.24	4837.81	151.18	2267.72	302.36	2570.08	10129.16

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.2-9 综合费计算表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围: K0+014.5勒德桥

序号	工程名称	措施费										企业管理费										规费				
		冬季 施工 增加 费	雨季 施工 增加 费	夜间 施工 增加 费	高原 地区 施工 增加 费	风沙 地区 施工 增加 费	沿海 地区 施工 增加 费	行车 干扰 施工 增加 费	施工 辅助 费	工地 转移 费	综合费用		基本 费用	主副 食运 费补 贴	职工 探亲 路费	职工 取暖 补贴	财务 费用	综合 费用	养老 保险 费	失业 保险 费	医疗 保险 费	工伤 保险 费	住房 公积 金	综合 费用		
											I	II														
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25		
14	现浇C30砼台帽及侧墙		19						133.9 6		19	133.9 6	456.6						456.6	502.1 3	15.69 7	235.3 7	31.38 6	266.7 6	1051. 33	
15	现浇C30砼挡块及支座垫石		1.73						11.1		1.73	11.1	38.76						38.76	42.56	1.33	19.95	2.66	22.61	89.11	
16	台背回填		10.25						32.85		10.25	32.85	173.1 8						173.1 8	52.05	1.63	24.4	3.25	27.65	108.9 8	
17	现浇钢筋混凝土矩形板		47.14						447.2 4		47.14	447.2 4	1550. 52						1550. 52	1340. 55	41.89 8	628.3 8	83.78 6	712.1 6	2806. 77	
18	现浇C40防水混凝土铺装		21.23						112.3 1		21.23	112.3 1	367.8 4						367.8 4	474.7	14.83 2	222.5 2	29.67 8	252.1 8	993.9 8	
19	桥面连续								9.65			9.65	38.35						38.35	37.49	1.17	17.58	2.34	19.92	78.5	
20	板式橡胶支座								7.85			7.85	31.2						31.2	22.59	0.71	10.59	1.41	12	47.29	
21	沥青麻絮伸缩缝		1.11						88.72		1.11	88.72 3	348.5						348.5	143.6	4.49	67.33	8.98	76.3 2	300.7 2	
22	现浇C30混凝土防撞护栏		25.34						221.8 6		25.34	221.8 6	749.3						749.3	942.8 3	29.46 5	441.9 5	58.93 8	500.8 05	1974. 05	
23	现浇C30砼搭板枕梁		21.59						151.2 5		21.59	151.2 5	507.0						507.0	623.2 8	19.48 2	292.1 3	38.95 9	331.0 86	1304. 86	
24	锥坡排水及防护		40.94						190.7 7		40.94	190.7 7	586.5						586.5	811.3 8	25.36 9	380.3 4	50.71 5	431.0 86	1698. 86	
25	台后排水		14.16						57.05		14.16	57.05 1	175.4						175.4 1	288.6 8	9.02 2	135.3 2	18.04 6	153.3 3	604.4 3	
	-													-										-	-	

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.2-9 综合费计算表

建设项目名称：西林县古障镇史革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

第 3 页 共 3 页 04-1表

序号	工程名称	措施费										企业管理费						规费							
		冬季施工增加费	雨季施工增加费	夜间施工增加费	高原地区施工增加费	风沙地区施工增加费	沿海地区施工增加费	行车干扰施工增加费	施工辅助费	工地转移费	综合费用		基本费用	主副食运费补贴	职工探亲路费	职工取暖补贴	财务费用	综合费用	养老保险费	失业保险费	医疗保险费	工伤保险费	住房公积金	综合费用	
											I	II													
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
26	泄水管		0.28						38.95		0.28	38.95	119.77						119.77	5.83	0.18	2.73	0.37	3.1	12.21
27	满堂木支架		52.41						218.8		52.41	218.8	672.77						672.77	1070.9	33.47	501.99	66.93	568.92	2242.2
28	编织袋围堰（高1.5m）		39.08						131.78		39.08	131.78	405.21						405.21	802.87	25.09	376.35	50.18	426.53	1681.01
29	M7.5浆砌片石挡墙		23.04						130.05		23.04	130.05	388.43						388.43	527.65	16.49	247.34	32.98	280.31	1104.77
30	合计:		977.67						4971.05		977.67	4971.05	15946.96						15946.96	17287.82	540.25	8103.67	1080.49	9184.15	36196.36

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.2-14 人工、材料、施工机械台班单价汇总表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

序号	名称	单位	代号	预算单价 (元)	备注	序号	名称	单位	代号	预算单价 (元)	备注
1	人工	工日	10010C1	101.25		19	铁钉混合规格	kg	2009030	5.65	
2	机械工	工日	10510C1	101.25		20	铸铁管	kg	2009033	3.42	
3	HPB300钢筋	t	20010C1	3708.93		21	石油沥青	t	3001001	4451.04	
4	HRB400钢筋	t	20010C2	3726.76		22	汽油92号	kg	3003002	8.98	
5	钢丝绳股丝6-7×19, 绳径7.1~9mm; 股丝6×37, 绳径14.1~15.5mm	t	2001019	6000		23	柴油0号, -10号, -20号	kg	3003003	7.3	
6	钢纤维扁丝切断型、钢丝切断型、高 强铰链型、剪切波纹型、剪切压痕型	t	2001020	6000		24	煤	t	3005001	561.95	
7	8~12号铁丝镀锌铁丝	kg	2001021	5.28		25	电	kW·h	3005002	0.73	
8	20~22号铁丝镀锌铁丝	kg	2001022	5.57		26	水	m ³	3005004	3.84	
9	型钢工字钢, 角钢	t	20030C4	3783.18		27	原木混合规格	m ³	4003001	889.57	
10	钢板Q235, δ=5~40mm	t	20030C5	5720		28	锯材中板 δ=19~35mm, 中方混合规格	m ³	4003002	1047.93	
11	钢管无缝钢管	t	20030C8	4301.22		29	PVC塑料管 (Φ50mm) Φ50mm	m	5001013	9.73	
12	钢模板各类定型大块钢模板	t	2003025	5247.26		30	塑料编织袋袋装砂井用	个	5001052	1.2	
13	组合钢模板	t	2003026	4766.68		31	硝铵炸药1号、2号岩石硝铵炸药	kg	5005002	12	
14	空心钢杆优质碳素工具钢	kg	20090C3	8.5		32	非电毫秒雷管导爆管长3~7m	个	5005008	15.9	
15	Φ50mm以内合金钻头Φ43mm	个	20090C4	35		33	导爆索爆速6000~7000m/s	m	5005009	2.05	
16	电焊条结422(502、506、507)3.2/4. 0/5.0	kg	2009011	6.64		34	土工布宽4~5m	m ²	5007001	5.6	
17	螺栓混合规格	kg	2009012	5.64		35	桥面防水涂料聚合物渗透水性桥面防 水涂料	kg	5009005	15.04	
18	铁件铁件	kg	2009022	5.65		36	油毛毡400g, 0.915m×21.95m	m ²	5009012	3.5	

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.2-14 人工、材料、施工机械台班单价汇总表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

09表

第 2 页 共 3 页

序号	名称	单位	代号	预算单价 (元)	备注	序号	名称	单位	代号	预算单价 (元)	备注
37	黏土堆方	m ³	5501003	28		55	斗容量1.0m ³ 履带式单斗挖掘机WY100 液压	台班	8001027	1174.46	
38	碎石土天然堆方	m ³	5501005	32.04		56	斗容量2.0m ³ 履带式单斗挖掘机WY200A 液压	台班	8001030	1478.3	
39	砂路面用堆方	m ³	5503004	160		57	斗容量1.0m ³ 履带式单斗挖掘机WK100 机械	台班	8001035	1033.08	
40	中(粗)砂混凝土、砂浆用堆方	m ³	5503005	150		58	斗容量1.0m ³ 轮胎式装载机ZL20	台班	8001045	573.85	
41	片石码方	m ³	5505005	135		59	功率120kW以内平地机F155	台班	8001058	1168.27	
42	碎石(2cm)最大粒径2cm堆方	m ³	5505012	145		60	功率75kW以内履带式拖拉机	台班	8001066	642.26	
43	碎石(4cm)最大粒径4cm堆方	m ³	5505013	145		61	机械自身质量10~12t光轮压路机3Y- 10/12	台班	8001080	503	
44	碎石(8cm)最大粒径8cm堆方	m ³	5505015	145		62	机械自身质量12~15t光轮压路机3Y- 12/15	台班	8001081	576.46	
45	碎石未筛分碎石统料堆方	m ³	5505016	145		63	机械自身质量18~21t光轮压路机3Y- 18/21	台班	8001083	739.61	
46	32.5级水泥	t	5509001	430		64	蛙式夯土机(200~620N·m)HW-280	台班	8001095	27.8	
47	42.5级水泥	t	5509002	450		65	容量4000L以内沥青洒布车JS-3500	台班	8003038	606.84	
48	钢筋混凝土电杆(7m)	根	5511002	264.1		66	混凝土电动真空吸水机组含吸垫 5m×5m	台班	8003079	134.92	
49	四氟板式橡胶组合支座GJZF4系列、 GYZF4系列	dm ³	6001002	59.83		67	电动混凝土切缝机(含锯片摊销费用) SLF	台班	8003085	202.97	
50	模数式伸缩装置240型	m	6003004	2393.16		68	出料容量250L以内强制式混凝土搅拌 机JD250	台班	8005002	166.33	
51	120/20 聚乙烯绝缘电力电缆规格 120/20	m	7001009	14.02		69	出料容量750L以内强制式混凝土搅拌 机JS750	台班	8005005	318.92	
52	其他材料费	元	7801001	1		70	出料容量400L以内灰浆搅拌机UJ325	台班	8005010	130.18	
53	设备摊销费	元	7901001	1		71	装载质量8t以内自卸汽车CD351	台班	8007014	668.83	
54	功率75kW以内履带式推土机TY100	台班	8001002	866.45		72	装载质量10t以内自卸汽车QD361	台班	8007015	747.22	

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.2-14 人工、材料、施工机械台班单价汇总表

建设项目名称：西林县古尊镇央草村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

序号	名称	单位	代号	预算单价 (元)	备注
73	容量6000L以内洒水汽车YCJ5102GSSEQ	台班	8007041	717.03	
74	容量10000L以内洒水汽车 YCJ5170GSSJN	台班	8007043	1093.21	
75	装载质量1.0t以内机动翻斗车F10A	台班	8007046	206.5	
76	提升质量12t以内汽车式起重机械QY12	台班	8009027	835.14	
77	提升质量25t以内汽车式起重机械QY25	台班	8009030	1342.51	
78	锯片直径500mm以内木工圆锯机MJ-106	台班	8015013	125.76	
79	容量32kV·A以内交流电弧焊机BX1-330	台班	8015028	168.92	
80	排气量9m3/min以内机动空气压缩机 VY-9/7	台班	8017049	710.65	
81	小型机具使用费	元	8099001	1	

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.3-1 分项工程预算计算数据表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目

编制范围: K0+014.5勒德桥

标准定额库版本号:

校验码:

第 1 页 共 6 页

21-1表

分项编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单介	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式
1	第一部分建筑安装工程费	桥长米	23.04	28300.64	652046.65		
101	临时工程	桥长米	23.04	103.04	25414.03		
10101	临时道路	m	60	134.75	8084.75		
1010101	临时便道(修建、拆除与维护)	m	60	134.75	8084.75		
101010101	路基土石方工程	m3	270	13.7	3698.73		
1-1-7-1	人工夯实填土	1000m3压土方	0.27	13699.01	3698.73	01.土方	
101010102	8cm泥结碎石面层	m2	210	20.89	4386.05		
2-2-1-1	人工摊铺泥结碎石面层(压实厚度8cm)	1000m2	0.21	20885.94	4386.05	04.路面	
10102	临时便桥、便涵	m	8	620.78	4966.21		
1010202	临时涵洞	m	8	620.78	4966.21		
1	外购Φ1000mm钢筋混凝土管(承插口II级) —含安装	m	8	620.78	4966.21	12.利润和税金	
10104	临时供电设施	总额	1	12363.04	12363.04		
7-1-5-1	架设输电线路	100m	1	12363.04	12363.04	06.构筑物 I	
102	路基工程	元			1409.46		
LJ01	场地清理	元					
LJ03	路基填方	m3	99	14.24	1409.46		
LJ0302	借土方填筑	m3	99	14.24	1409.46		
1-1-9-5	—容量1.0m3以内挖掘机挖装普通土	1000m3天然密实方	0.099	3488.66	345.38	01.土方	
1-1-11-5	装载质量10t以内自卸汽车运土第一个1km	1000m3天然密实方	0.099	6376.35	631.26	03.运输	
1-1-18-10	三、四级公路填方路基,自身质量10~12t 无轮压路机碾压土方	1000m3压土方	0.099	4371.98	432.83	01.土方	
103	路面工程	元			27185.74		
LM02	水泥混凝土路面	m2	205	132.61	27185.74		
LM0203	路面基层	m2	227	23.48	5329.64		

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-1 分项工程预算计算数据表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目									
编制范围：K0+014.5勒德桥									
标准定额库版本号：					校验码：		第 2 页 共 6 页		21-1表
分项编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单价	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式		
LM0203C4	级配碎石基层厚8cm	m2	227	23.48	5329.64				
2-2-2-2换	人工摊铺级配碎石基层(拖拉机带铧犁拌和,压实厚度8cm)	1000m2	0.227	23478.61	5329.64	04.路面	实际厚度(cm): 8cm;		
LM0205	水泥混凝土面层	m2	205	106.62	21856.1				
LM0205C1	水泥混凝土厚18cm	m2	205	106.62	21856.1				
2-2-17-1换	人工铺筑混凝土路面厚度18cm	1000m2路面	0.205	106615.1	21856.1	04.路面	实际厚度(cm): 15cm; 普C30-32.5-4 换 普C30-42.5-4;		
104	桥梁涵洞工程	桥长米	23.04	25538.25	588401.3				
10402	小桥工程	m	23.04	25538.25	588401.3				
1040202	勒德桥	m	126.72	4643.32	588401.3				
QL01	基础工程	m3	183	712.3	130350.98				
QL0101	扩大基础	m3	183	597.39	109322.02				
QL010101	现浇C25混凝土基础	m3	183	597.39	109322.02				
4-6-1-3换	实体式墩台混凝土基础(梁板式上部构造)	10m3实体	18.3	5633.74	103097.39	07.构造物 II	片C15-32.5-8 换 普C25-32.5-2;		
4-11-11-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	1.8666	839.24	1566.52	03.运输			
4-11-11-4	容量750L以内混凝土搅拌机拌和	10m3	18.666	249.55	4658.11	06.构造物 I			
QL0107	挖基坑	m3	585	35.95	21028.96				
QL010701	挖土方	m3	468	21.32	9976.17				
4-1-3-3	斗容量1.0m3以内挖掘机挖基坑≤1500m3土方	1000m3	0.468	21316.6	9976.17	01.土方			
QL010702	挖石方	m3	117	57.72	6752.81				
4-1-3-5	机械挖基坑≤1500m3石方	1000m3	0.117	57716.3	6752.81	07.构造物 II			
QL010703	弃土方	m3	468	6.94	3246.38				
1-1-11-3	装载质量8t以内自卸汽车运土第一个1km	1000m3天然密实方	0.468	6936.72	3246.38	03.运输			
QL010704	弃石方	m3	117	9.01	1053.6				

编制：灵明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.3-1 分项工程预算计算数据表

编制范围: K0+014.5勒德桥					标准定额库版本号:		校验码:		第 3 页		共 6 页		21-1表	
分项目编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单价	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式							
1-1-1-17	装载质量8t以内自卸汽车运石第一个1km	100m3天然 密实方	0.117	9005.14	1053.6	03. 运输								
QL02	下部构造				201894.36									
QL020	现浇C30砼台身	m3	210.8	813.02	171385.17									
4-6-2-4换	梁板桥实体式墩台混凝土(高10m以内)	10m3实体	21.08	7582.64	159842.05	07. 构造物 II	片C15-32.5-8 换 普C30-42.5-2;							
3-1-6-5	钢筋网	1t	0.623	7019.04	4372.86	10. 钢材及钢结构(一般)								
4-11-1-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	2.1502	839.24	1804.53	03. 运输								
4-11-1-4	容量750L以内混凝土搅拌机拌和	10m3	21.5016	249.55	5365.73	06. 构造物 I								
QL0203	现浇C30砼台帽及侧墙	m3	10.42	1999.47	20834.44									
4-6-3-1换	混凝土墩、台帽非泵送	10m3实体	1.042	8046.69	8384.65	07. 构造物 II	普C30-32.5-4 换 普C30-42.5-4;							
4-6-3-5换	现场加工桥(涵)台帽钢筋	1t	2.093	5778.95	12095.35	10-1. 钢材及钢结构 (桥梁)	钢筋抽换: [2001001] 换 [2001002];							
4-11-1-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	0.1063	839.23	89.21	03. 运输								
4-11-1-4	容量750L以内混凝土搅拌机拌和	10m3	1.0628	249.55	265.22	06. 构造物 I								
QL0203	现浇C30砼挡块及支座垫石	m3	0.5	3704.24	1852.12									
4-6-2-87换	板式支座垫石混凝土	10m3实体	0.05	11512.08	575.6	07. 构造物 II	普C30-32.5-4 换 普C30-42.5-4;							
4-6-2-88	现场加工支座垫石钢筋	1t	0.2296	5485.64	1259.5	10-1. 钢材及钢结构 (桥梁)								
4-11-1-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	0.0051	839.61	4.28	03. 运输								
4-11-1-4	容量750L以内混凝土搅拌机拌和	10m3	0.051	249.57	12.73	06. 构造物 I								
QL0204	台背回填	m3	135	57.95	7822.63									
借[桂2020养预]4-4-3-8换	台背碎石土回填	100m3	1.35	5794.54	7822.63	01. 土方	[5503007] 换 [5501005];							
QL03	上部构造	m3	30.4	2417.89	73503.94									
QL0304	现浇钢筋混凝土矩形板	m3	30.4	2417.89	73503.94									
4-6-8-1换	现浇混凝土矩形板上部构造	10m3实体	3.04	7904.3	24029.08	07. 构造物 II	普C30-32.5-4 换 普C30-42.5-4;							

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-1 分项工程预算计算数据表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目

编制范围: KO+014.5勒德桥

标准定额库版本号:

校验码:

第 4 页

共 6 页

21-1表

分项编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单价	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式
4-7-22-10换	现浇刚架拱头混凝土	10m3实体	0.1	11407.93	1140.79	07. 构造物 II	普C35-32.5-2 换 普C30-32.5-2;
4-6-8-4换	现场加工现浇矩形板上部构造钢筋	1t	8.9853	5264.16	47300.02	10-1. 钢材及钢结构 (桥梁)	钢筋抽换: [2001001] 换 [2001002];
4-11-11-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	0.3101	839.24	260.25	03. 运输	
4-11-11-4	容量750L以内混凝土搅拌机拌和	10m3	3.1008	249.55	773.81	06. 构造物 I	
QL04	桥面铺装	m3	11.9	1917.96	22823.78		
QL0402	现浇C40防水混凝土铺装	m3	11.9	1719.4	20460.84		
4-6-13-5换	桥面行车道铺装防水混凝土面层非泵送	10m3	1.19	7439.05	8852.47	04. 路面	防水混凝土抽换: 防C30-32.5-4 换 防C40-42.5-4;
4-6-13-8换	桥面行车道铺装水泥及防水混凝土钢筋(直径8mm以上)	1t	1.2311	5982.98	7365.65	10-1. 钢材及钢结构 (桥梁)	钢筋抽换: [2001001] 换 [2001002];
4-11-4-6	桥面防水剂(防水层)	1000m2	0.1263	30387.46	3837.94	07. 构造物 II	
4-11-11-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	0.1214	839.23	101.88	03. 运输	
4-11-11-4	容量750L以内混凝土搅拌机拌和	10m3	1.2138	249.55	302.9	06. 构造物 I	
QL0404	桥面连续	t	0.431	5482.46	2362.94		
4-6-8-5换	现场加工现浇连续板上部构造钢筋	1t	0.431	5482.46	2362.94	10-1. 钢材及钢结构 (桥梁)	钢筋抽换: [2001001] 换 [2001002];
QL05	桥梁附属结构				110386.95		
QL0501	桥梁支座	个	10	202.63	2026.34		
QL050104	板式橡胶支座	dm3	11.618	174.41	2026.34		
4-7-27-4	安装四氟板式橡胶组合支座	1dm3	11.618	174.41	2026.34	10-1. 钢材及钢结构 (桥梁)	
QL0502	伸缩缝	m	5.5	3406.31	18734.68		
QL050202	沥青麻絮伸缩缝	m	5.5	3406.31	18734.68		
4-11-7-1	模数式伸缩缝(伸缩量480mm以内)	1m	5.5	3159.73	17378.49	10-1. 钢材及钢结构 (桥梁)	
4-11-7-5换	模数式伸缩缝预留槽混凝土	10m3	0.05	9591.72	479.59	07. 构造物 II	普C50-42.5-2 换 普C40-42.5-4;

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-1 分项工程预算计算数据表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

标准定额库版本号：

校验码：

第 5 页

共 6 页

21-1表

分项目编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单价	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式
4-11-1-6	模数式伸缩缝预留槽钢筋	1t	0.1382	6343.05	876.61	10-1. 钢材及钢结构 (桥梁)	
QL050	护栏与护网	m	46.08	727.66	33530.75		
QL050.04	现浇C30混凝土防撞护栏	m	46.08	727.66	33530.75		
5-1-1-5换	现浇钢筋混凝土防撞护栏墙体混凝土	10m3实体	1.88	8039.43	15114.12	07. 构造物 II	普C25-32.5-4 换 普C30-42.5-4;
5-1-1-6换	现浇钢筋混凝土防撞护栏墙体钢筋	1t	3.0736	5991.88	18416.63	10. 钢材及钢结构(一般)	钢筋抽换: [2001001] 换 [2001002];
QL050	现浇C30砼搭板枕梁	m3	15.8	1437.93	22719.24		
4-6-1-1-1换	混凝土搭板	10m3实体	1.58	6887.88	10882.85	07. 构造物 II	普C30-32.5-4 换 普C30-42.5-4;
4-6-1-3	现场加工桥头搭板钢筋	1t	2.0018	5644.39	11298.93	10-1. 钢材及钢结构 (桥梁)	
4-11-1-20	装载质量1t以内机动翻斗车运混凝土第一个100m	100m3	0.1612	839.23	135.28	03. 运输	
4-11-1-4	容量750L以内混凝土搅拌机拌和	10m3	1.6116	249.55	402.18	06. 构造物 I	
QL050	锥坡排水及防护	m3	50.5	462.35	23348.67		
4-5-2-1换	浆砌片石基础、护底、截水墙	10m3	2.2	4187.01	9211.43	07. 构造物 II	[5509001] 换 [5509002];
4-11-5-1换	基础垫层填砂砾(砂)	10m3实体	0.95	2353.79	2711.1	07. 构造物 II	[5503007] 换 [5503004];
4-11-1-1	锥坡填土	10m3实体	4	707.98	2831.93	07. 构造物 II	
1-4-1-2换	浆砌片石护坡(坡高10m以内)	10m3实体	1.9	4523.27	8594.22	07. 构造物 II	[5509001] 换 [5509002];
QL050	台后排水	m3	32.4	211.8	6862.46		
4-11-3-3换	台背排水	10m3实体	3.24	2118.04	6862.46	07. 构造物 II	[4013002] 换 [5007001];
QL050	泄水管	套	18	175.82	3164.81		
4-11-1-13换	泄水管	10个	1.8	1758.23	3164.81	07. 构造物 II	[2009033] 量 403.0;
QL06	其他工程	桥长米	23.04	2145.89	49441.29		
QL060	满堂木支架	m2	97.5	180.95	17642.36		
4-9-3-1	满堂式木支架墩台高6m以内	10m2	9.75	1809.47	17642.36	07. 构造物 II	
QL060	编织袋围堰(高1.5m)	m	42	277.45	-11652.87		

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥

分项编号: 101010102

工程名称: 8cm泥结碎石面层

单位: m2

数量: 210

单价: 20.89

第 2 页共 53 页

21-2表

代 号	工 程 项 目		泥结碎石路面										合 计					
	工 程 细 目		人工摊铺泥结碎石面层(压实厚度8cm)															
	定 额 单 位		1000m2															
	工 程 数 量		0.21															
	定 额 表 号		2~2~1~1															
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)			
1001001	人工	工日	101.25	18.1	3.801	384.85						3.801			384.85			
3005004	水	m3	3.84	21	4.41	16.93						4.41			16.93			
5501003	黏土堆方	m3	28	22.86	4.801	134.42						4.801			134.42			
5505016	碎石未筛分碎石统料堆方	m3	145	98.99	20.788	3014.25						20.788			3014.25			
8001081	机械自身质量12~15t光轮压路机3Y-12/15	台班	576.46	0.25	0.053	30.26						0.053			30.26			
8001083	机械自身质量18~21t光轮压路机3Y-18/21	台班	739.61	0.45	0.095	69.89						0.095			69.89			
9999001	定额基价	元	1	10229	2148	2148						2148			2148			
	直接费	元				3650.61									3650.61			
	措施费	I		505.94	0.94%	4.76									4.76			
		II		2148.13	0.818%	17.57									17.57			
	企业管理费	元		2148.13	2.427%	52.14									52.14			
	规费	元		399.73	33.5%	133.91									133.91			
	利润	元		2222.6	7.42%	164.92									164.92			
	税金	元		4023.9	9%	362.15									362.15			
	金额合计	元				4386.05									4386.05			

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥				工程名称: 临时深洞				单位: m				数量: 8				单价: 620.78				第 3 页共 53 页				21-2表	
代 号	工 程 项 目		外购Φ1000mm钢筋混凝土管(承插口Ⅱ级)---含安装																						
	工 程 细 目		外购Φ1000mm钢筋混凝土管(承插口Ⅱ级)---含安装																						
	定 额 单 位		m																						
	工 程 数 量		8																						
	定 额 表 号		1																						
9999001	工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	合 计						
	定额基价		元	1	530	8	4241										4241		4241						
直接费		元					4241.44												4241.44						
措施费		I	元																						
		II	元																						
企业管理费		元																							
规费		元																							
利润		元			4241.44	7.42%	314.72												314.72						
税金		元			4556.16	9%	410.05												410.05						
金额合计		元					4966.21												4966.21						

编制: 吴明兰(西乡县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 临时供电设施			单位: 总额			数量: 1			单价:			12363.04			第 4 页共 53 页			21-2表		
代 号			工 程 项 目			架设输电线路												合 计					
			工 程 细 目			架设输电线路																	
			定 额 单 位			100m																	
			工 程 数 量			1																	
			定 额 表 号			7~1~5~1																	
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)						
1001001	人工	工日	10.25	4.5	4.5	455.63										4.5	455.63						
2001021	8~12号铁丝镀锌铁丝	kg	5.28	4.2	4.2	22.18										4.2	22.18						
2003004	型钢工字钢,角钢	t	3783.18	0.02	0.015	56.75										0.015	56.75						
2003005	钢板Q235, δ=5~40mm	t	5720	0.05	0.05	286										0.05	286						
2009028	铁件铁件	kg	5.65	11.5	11.5	64.98										11.5	64.98						
5511002	钢筋混凝土电杆(7m)	根	234.1	3	3	792.3										3	792.3						
7001009	120/20 聚乙烯绝缘电力电缆 规格120/20	m	14.02	315	315	4416.3										315	4416.3						
7801001	其他材料费	元	1	157.8	157.8	157.8										157.8	157.8						
7901001	设备摊销费	元	1	3697.9	3697.9	3697.9										3697.9	3697.9						
9999001	定额基价	元	1	9843	9843	9843										9843	9843						
	直接费	元				9949.82											9949.82						
	措施费	I		478.26	0.622%	2.97											2.98						
		II		9842.88	1.201%	118.21											118.21						
	企业管理费	元		9842.88	3.587%	353.06											353.06						
	规费	元		455.62	33.5%	152.63											152.63						
	利润	元		10317.13	7.42%	765.53											765.53						
	税金	元		11342.24	9%	1020.8											1020.8						
	金额合计	元				12363.04											12363.04						

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
分项编号: LM020304

工程名称: 级配碎石基层 厚8cm

单位: m2

数量: 227

单价: 23.48

第 6 页共 53 页

21-2表

代 号	工 程 项 目		级配碎石路面				合 计					
	工 程 细 目		人工摊铺级配碎石基层(拖拉机带铧犁 拌和,压实厚度8cm)									
	定 额 单 位		1000m2									
	工 程 数 量		0.227									
	定 额 表 号		2~2~2~2改									
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
1001001	人工	工日	101.25	11.5	2.611	264.31					2.611	264.31
5505016	碎石未筛分碎石统料堆方	m3	145	122.66	27.844	4037.35					27.844	4037.35
7901001	设备摊销费	元	1	2.1	0.477	0.48					0.477	0.48
8001066	功率75kW以内履带式拖拉机	台班	642.26	C.22	0.05	32.07					0.05	32.07
8001081	机械自身质量12~15t光轮压路机3Y-12/15	台班	576.46	C.12	0.027	15.7					0.027	15.7
8001083	机械自身质量18~21t光轮压路机3Y-18/21	台班	739.61	0.8	0.182	134.31					0.182	134.31
8007043	容量10000L以内洒水汽车 YG15170GSSIN	台班	1093.21	C.08	0.018	19.85					0.018	19.85
9999001	定额基价	元	1	11419	2592	2592					2592	2592
	直接费	元				4504.09						4504.09
	措施费	I		482.94	0.94%	4.54						4.54
		II		2592.03	0.818%	21.2						21.2
	企业管理费	元		2592.03	2.427%	62.91						62.91
	规费	元		292.35	33.5%	97.94						97.94
	利润	元		2680.67	7.42%	198.91						198.91
	税金	元		4889.58	9%	440.06						440.06
	金额合计	元				5329.64						5329.64

表A.0.3-2 分项工程预算表

编制范围: K0+01~.5勒德桥			工程名称: 水泥混凝土 厚18cm			单位: m2			数量: 205			单价: 105.62			第 7 页共 53 页			21-2表		
代 号			工 程 项 目			普通混凝土														
			工 程 细 目			人工铺筑混凝土路面厚度18cm														
			定 额 单 位			1000m2路面														
			工 程 数 量			0.205														
			定 额 表 号			2~2~17~1改														
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	数量	合计				
1001001	人工	工日	101.25	159.6	32.718	3312.7							32.718	3312.7		3312.7				
2001001	HPF300钢筋	t	3708.93		0.001	3.04							0.001			3.04				
2005004	型钢工字钢,角钢	t	3783.18	0.05	0.01	37.23										37.23				
3001001	石油沥青	t	4451.04	0.09	0.019	83.03										83.03				
3005001	煤	t	561.95	0.02	0.004	2.07										2.07				
3005004	水	m3	3.84	27	5.535	21.25										21.25				
4005002	锯材中板 δ = 19~35mm, 中方 混合规格	m3	1047.93	0.07	0.014	15.04										15.04				
5505005	中(粗)砂混凝土、砂浆用 堆方	m3	150	84.46	17.313	2597.02										17.313			2597.02	
5505013	碎石(4cm) 最大粒径4cm堆 方	m3	145	154.22	31.616	4584.31										31.616			4584.31	
5505002	42.5级水泥	t	450	65.18	13.361	6012.67										13.361			6012.67	
7805001	其他材料费	元	1	257.4	52.767	52.77										52.767			52.77	
8005079	混凝土电动真空吸水机组含 吸盘5m×5m	台班	134.92	2.47	0.506	68.32										0.506			68.32	
8005085	电动混凝土切割机(含锯片摊 销费用)SLF	台班	202.97	2.49	0.51	103.44										0.51			103.44	
8005002	出料容量250L以内强制式混 凝土搅拌机JD250	台班	166.33	4.76	0.976	162.3										0.976			162.3	
8005043	容量10000L以内洒水汽车 YG 5170GSS IN	台班	1093.21	1.12	0.23	251										0.23			251	
8095001	小型机具使用费	元	1	226.1	46.351	46.35										46.351			46.35	
9995001	定额基价	元	1	65846	13498	13498										13498			13498	
																			-	

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 水泥混凝土 厚18cm			单位: m2			数量: 205			单价: 106.62			第 8 页共 53 页			21-2表
代 号			工 程 项 目		普通混凝土										合 计			
			工 程 细 目		人工铺筑混凝土路面厚度18cm													
			定 额 单 位		1000m2路面													
			工 程 数 量		0.205													
			定 额 表 号		2~2~17~1改													
			工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)		
			直接费	I													17352.55	
					措施费	II												38.82
			企业管理费		元		13498.49	2.427%	327.61								110.42	
					元		3537.61	33.5%	1185.1								327.61	
			规费		元		13975.34	7.42%	1036.97								1185.1	
					元		20051.47	9%	1804.63								1036.97	
			税金		元												1804.63	
					元												21856.1	
			金额合计		元												21856.1	

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇C25混凝土基础		单位: m3	数量: 183	单价: 597.39	第 9 页共 53 页		21-2表		
代 号	工 程 项 目		基础、承台及支撑梁		混凝土运输		混凝土搅拌机拌和				
	工 程 细 目		实体式墩台混凝土基础(梁板式上部构造)		装载质量1t以内机动翻斗车运混凝土第一个100m		容量750L以内混凝土搅拌机拌和				
	定 额 单 位		10m3实体		100m3		10m3				
	工 程 数 量		18.3		1.8666		18.666				
	定 额 表 号		4~6~1~3改		4~11~11~20		4~11~11~4				
号	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)
	100.001 人工	工日	101.25	5.5	100.65	10190.81		1	18.666	119.316	12080.75
	2003025 钢模板各类定型大块钢模板	t	5247.26	0.02	0.311	1632.42				0.311	1632.42
	2003013 螺栓混合规格	kg	5.64	0.4	7.32	41.28				7.32	41.28
	2003028 铁件铁件	kg	5.65	3.5	64.05	361.88				64.05	361.88
	3005004 水	m3	5.84	12	219.6	843.26				219.6	843.26
	5503005 中(粗)砂混凝土、砂浆用堆方	m3	150	4.9	89.597	13439.52				89.597	13439.52
	5505012 碎石(2cm)最大粒径2cm堆方	m3	145	8.16	149.328	21652.56				149.328	21652.56
	5503001 32.5级水泥	t	430	3.75	68.691	29540.23				68.691	29537.08
	780.001 其他材料费	元	1	15.7	287.31	287.31				287.31	287.31
	8005005 出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92					0.2	3.733	1190.59	1190.59
	8007046 装载质量1.0t以内机动翻斗车F10A	台班	206.5				2.94	5.488	1133.23	5.488	1133.23
	8009030 提升质量25t以内汽车式起重机械Q25	台班	1342.51	0.17	3.111	4176.55				3.111	4176.55
	8093001 小型机具使用费	元	1	9	164.7	164.7				164.7	164.7
	9999001 定额基价	元	1	3286	60142	60142	625	1167	1167	3274	64584

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇C25混凝土基础		单位: m3		数量: 183		单价: 597.39		第 10 页共 53 页		21-2表	
代 号	工 程 项 目		基础、承台及支撑梁			混凝土运输			混凝土搅拌机拌和			合 计	
	工 程 细 目		实体式墩台混凝土基础(梁板式上部构造)			装载质量1t以内机动翻斗车运混凝土第一个100m			容量750L以内混凝土搅拌机拌和				
	定 额 单 位		10m3实体			100m3			10m3				
	工 程 数 量		18.3			1.8666			18.666				
	定 额 表 号		4~6~1~3改			4~11~11~20			4~11~11~4				
	工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
	直接费		元					82330.53			1133.23		3080.53
	措施费	I	元		15080.86	0.742%	111.9	1167.37	0.959%	11.2	3274.13	0.622%	20.37
		II	元		60144.43	1.537%	924.42	1167.37	0.154%	1.8	3274.13	1.201%	39.32
	企业管理费		元		60144.43	4.726%	2842.43	1167.37	1.374%	16.04	3274.13	3.587%	117.44
	规费		元		10820.79	33.5%	3624.97	555.64	33.5%	186.14	2267.92	33.5%	759.75
	利润		元		64023.18	7.42%	4750.52	1196.4	7.42%	88.77	3451.25	7.42%	256.08
	税金		元		94584.77	9%	8512.63	1437.18	9%	129.35	4273.49	9%	384.61
	金额合计		元				103097.39		-566.52				4658.11
													109322.02

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥				工程名称: 弃石方				单位: m3				数量: 117				单价: 9.01				第 14 页共 53 页				21-2表	
分项编号: QL010704																									
代 号	工 程 项 目			自卸汽车运土、石方																					
	工 程 细 目			装载质量8t以内自卸汽车运石第一个1km																					
	定 额 单 位			1000m3天然密实方																					
	工 程 数 量			0.117																					
	定 额 表 号			1~1~11~17																					
8007014	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	838.09				
	装载质量8t以内自卸汽车	台班	668.83	10.71	1.253	838.09													1.253	838.09					
9999001	定额基价	元	1	7285	852	852													852	852					
	直接费	元				838.09															838.09				
	措施费	I	元	852.31	0.959%	8.17															8.17				
		II	元	852.31	0.154%	1.31															1.31				
	企业管理费	元		852.31	1.374%	11.71															11.71				
	规费	元		126.87	33.5%	42.5															42.5				
	利润	元		873.52	7.42%	64.82															64.82				
	税金	元		966.61	9%	87															87				
-	金额合计	元				1053.6															1053.6				

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇C30砼台身		单位: m3		数量: 210.8		单价:		815.02		第 15 页共 53 页		21-2表	
分项编号: QL0201		工 程 项 目		实 体 式 墩 台		锚杆及金属网		混凝土运输		混凝土搅拌机拌和					
代 号	工 程 细 目		梁板桥实体式墩台混凝土(高10m以内)		钢筋网		装载质量1t以内机动翻斗车运混凝土第一个100m		容量750L以内混凝土搅拌机拌和						
	定 额 单 位		10m3实体		1t		100m3		10m3						
	工 程 数 量		21.08		0.623		2.1502		21.5016						
	定 额 表 号		4~6~2~4改		3~1~6~5		4~11~11~20		4~11~11~4						
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
1001001	人工	工日	101.25	11.5	242.42	24545.03	12.8	7.974	807.41				1	21.502	2177.04
2001001	HPB300钢筋	t	3708.93				1.03	0.639	2368.43						
2001019	钢丝绳股丝6-7×19, 绳径7.1~9mm; 股丝6×37, 绳径14.1~15.5mm	t	6000		0.042	252.96									
2001021	8~12号铁丝镀锌铁丝	kg	5.28	0.16	3.373	17.81									
2001022	20~22号铁丝镀锌铁丝	kg	5.57				0.9	0.561	3.12						
2003008	钢管无缝钢管	t	4301.22	0.01	0.19	816.03									
2003025	钢模板各类定型大块钢模板	t	5247.26	0.05	1.033	5420									
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	3.64				6.3	3.925	26.06						
2009013	螺栓混合规格	kg	5.64	4.99	105.189	593.27									
2009028	铁件铁件	kg	5.65	2.95	62.186	351.35									
2009030	铁钉混合规格	kg	5.65	0.14	2.951	16.67									
3005004	水	m3	3.84	12	252.96	971.37									
4003002	锯材中板 δ = 19~35mm, 中方混合规格	m3	1047.93	0.02	0.422	441.81									
5503005	中(粗)砂混凝土、砂浆用堆方	m3	150	4.9	103.208	15481.15									
5505012	碎石(2cm)最大粒径2cm堆方	m3	145	3.06	169.863	24630.08									
5509002	42.5级水泥	t	450	3.96	83.426	37545.59									
7801001	其他材料费	元	1	32.7	1743.316	1743.32									
8005005	出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92	-									0.2	-	4.3
															1371.46

编制: 吴明兰(西林县财政投资评审中心) 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: KO+014.5勒德桥				工程名称: 现浇C30砼台身				单位: m3				数量: 210.8				单价:				813.02				第 16 页共 53 页				21-2表			
代 号				工 程 项 目		实 体 式 墩 台				锚 杆 及 金 属 网				混 凝 土 运 输				混 凝 土 搅 拌 机 拌 和													
				工 程 细 目		梁板桥实体式墩台混凝土(高10m以内)				钢筋网				装载质量1t以内机动翻斗车运混凝土 第一个100m				容量750L以内混凝土搅拌机拌和													
				定 额 单 位		10m3实体				1t				100m3				10m3													
				工 程 数 量		21.08				0.623				2.1502				21.5016													
				定 额 表 号		4~6~2~4改				3~1~6~5				4~11~11~20				4~11~11~4													
8007046	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)													
	装载质量1.0t以内机动翻斗车F10A	台班	206.5										2.94	6.321	1305.38																
8009030	提升质量25t以内汽车式起重 机QY25	台班	1342.51	0.36	7.589	10188.04																									
8015028	容量32kV·A以内交流电弧焊 机BX1-330	台班	168.92				1.5	0.935	157.86																						
8099001	小型机具使用费	元	1	10.1	212.908	212.91	22.7	14.142	14.14																						
9999001	定额基价	元	1	4825	101711	101711	5117	3188	3188				625	1345	1345	175	3772	3772													
	直接费	元				123227.37			3377.02						1305.41			3548.5													
	措施费	I	元	36269.08	0.742%	269.12	1033.82			1344.7	0.959%		12.9	3771.51	0.622%			23.46													
		II	元	101714.2	1.537%	1563.35	3187.58	0.564%	17.98	1344.7	0.154%		2.07	3771.51	1.201%			45.3													
	企业管理费	元		101714.2	4.726%	4807.01	3187.58	2.242%	71.47	1344.73	1.374%		18.48	3771.51	3.587%			135.28													
	规费	元		26081.76	33.5%	8737.39	902.03	33.5%	302.18	640.06	33.5%		214.42	2612.44	33.5%			875.17													
	利润	元		108353.68	7.42%	8039.84	3277.02	7.42%	243.16	1378.17	7.42%		102.26	3975.55	7.42%			294.99													
	税金	元		146644.08	9%	13197.97	4011.8	9%	361.06	1655.53	9%		149	4922.69	9%			443.04													
	金额合计	元				159842.05			4372.86				1804.53					5365.73													

编制: 吴明兰(西林县财政投资评审中心) 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 工程名称: 现浇C30砼台身
 单位: m3
 数量: 210.8
 单价: 813.02
 第 17 页共 53 页
 21-2表

代 号	工 程 项 目																				合 计	
	工 程 细 目																					
	定 额 单 位																					
	工 程 数 量																					
	定 额 表 号																					
工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	
1001001	人工	工日	101.25															271.896		27529.47		
2001001	HPB300钢筋	t	3708.93															0.639		2368.43		
2001019	钢丝绳股丝6-7×19，绳径7.1~9mm；股丝6×37，绳径14.1~15.5mm	t	6000															0.042		252.96		
2001021	8~12号铁丝镀锌铁丝	kg	5.28															3.373		17.81		
2001022	20~22号铁丝镀锌铁丝	kg	5.57															0.561		3.12		
2003008	钢管无缝钢管	t	4301.22															0.19		816.03		
2003025	钢模板各类定型大块钢模板	t	5247.26															1.033		5420		
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	6.64															3.925		26.06		
2009013	螺栓混合规格	kg	5.64															105.189		593.27		
2009028	铁件铁件	kg	5.65															62.186		351.35		
2009030	铁钉混合规格	kg	5.65															2.951		16.67		
3005004	水	m3	3.84															252.96		971.37		
4003002	锯材中板 δ = 19~35mm，中方混合规格	m3	1047.93															0.422		441.81		
5503005	中（粗）砂混凝土、砂浆用堆方	m3	150															103.208		15481.15		
5505012	碎石（2cm）最大粒径2cm堆方	m3	145															169.863		24630.08		
5509002	42.5级水泥	t	450															83.426		37541.79		
7801001	其他材料费	元	1															1743.316		1743.32		
8005005	出料容量750L以内强制式混凝土搅拌机 JS750	台班	318.92															4.3		1371.46		

编制: 吴明兰(西林县财政投资评审中心) 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 工程名称: 现浇C30砼台帽及侧墙
 单位: m3
 数量: 10.42
 单价: 1999.47
 第 19 页共 53 页
 21-2表

代 号	工 程 项 目		混 凝 土				钢 筋		混 凝 土 运 输			混 凝 土 搅 拌 机 拌 和	
	工 程 细 目		混 凝 土 墩、台 帽 非 泵 送	现 场 加 工 桥 (涵) 台 帽 钢 筋	装 载 质 量 1t 以 内 机 动 翻 斗 车 运 混 凝 土 第 一 个 100m	容 量 750L 以 内 混 凝 土 搅 拌 机 拌 和							
	定 额 单 位		10m3实 体	1t	100m3	10m3							
	工 程 数 量		1.042	2.093	0.1063	1.0628							
	定 额 表 号		4~6~3~1改	4~6~3~5改	4~11~11~20	4~11~11~4							
工、料、机 名 称		单 位	单 价 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	
1001001	人 工	工 日	101.25	12.4	12.921	1308.23	6.9	14.442	1462.22		1	107.61	
2001002	HRB400钢筋	t	3725.76				1.03	2.145	7995.11				
2001022	20~22号铁丝镀锌铁丝	kg	5.57				2.86	5.986	33.34				
2003025	钢模板各类定型大块钢模板	t	5247.26	0.05	0.051	267.91							
2003011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	5.64				2.23	4.667	30.99				
2003013	螺栓混合规格	kg	5.64	5.91	6.158	34.73							
2005028	铁件铁件	kg	5.65	3.48	3.626	20.49							
3005004	水	m3	3.84	12	12.504	48.02							
5505005	中(粗)砂混凝土、砂浆用	m3	150	4.69	4.889	733.36							
5505013	碎石(4cm)最大粒径4cm堆	m3	145	8.57	8.928	1294.54							
5505002	42.5级水泥	t	450	3.62	3.773	1697.89							
780.001	其他材料费	元	1	86.2	89.82	89.82							
8005005	出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92							0.2	0.213	67.79	
8005046	装载机1.0t以内机动翻斗车F10A	台班	206.5							2.94	0.312	64.53	
8005030	提升质量25t以内汽车式起重机械QY25	台班	1342.51	0.66	0.688	923.27							
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	168.92				0.32	0.67	113.14				
8095001	小型机具使用费	元	1	11.4	11.879	11.88	18.8	39.348	39.35				
9999001	定额基价	元	1	5147	5364	5364	4167	8721	8721	625	175	186	

编制: 吴明兰(西林县财政投资评审中心)
 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇C30砼台帽及侧墙		单位: m3		数量: 10.42		单价:		1999.47		第 20 页共 53 页		21-2表		
代 号	工 程 项 目		混凝土			钢筋			混凝土运输			混凝土搅拌机拌和				
	工 程 细 目		混凝土墩、台帽非泵送			现场加工桥(涵)台帽钢筋			装载质量1t以内机动翻斗车运混凝土 第一个100m			容量750L以内混凝土搅拌机拌和				
	定 额 单 位		10m3实体			1t			100m3			10m3				
	工 程 数 量		1.042			2.093			0.1063			1.0628				
	定 额 表 号		4~6~3~1改			4~6~3~5改			4~11~11~20			4~11~11~4				
	工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
	直接费		元				6430.14			9674.15			64.54			175.4
	措施费		I	元	2317.77	0.742%	17.2	1697.6			66.47	0.959%	0.64	186.43	0.622%	1.16
			II	元	5363.57	1.537%	82.44	8720.73	0.564%	49.15	66.47	0.154%	0.1	186.43	1.201%	2.24
	企业管理费		元		5363.57	4.726%	253.48	8720.73	2.242%	195.52	66.48	1.374%	0.91	186.42	3.587%	6.69
	规费		元		1447.49	33.5%	484.91	1530.04	33.5%	512.55	31.64	33.5%	10.6	129.13	33.5%	43.26
	利润		元		5716.68	7.42%	424.18	8965.43	7.42%	665.24	68.13	7.42%	5.06	196.51	7.42%	14.58
	税金		元		7692.34	9%	692.31	11096.66	9%	998.7	81.84	9%	7.37	243.32	9%	21.9
	金额合计		元				8384.65			12095.35			89.21			265.22

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 分项编号: QL0202
 工程名称: 现浇C30砼台帽及侧墙
 单位: m3
 数量: 10.42
 单价: 1959.47
 第 21 页共 53 页
 21-2表

代 号	工 程 项 目		合 计									
	工 程 细 目											
	定 额 单 位											
	工 程 数 量											
	定 额 表 号											
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	金额(元)
1001001	人工	工日	101.25							28.425		2878.07
2001002	HRB400钢筋	t	3726.76							2.145		7995.11
2001022	20~22号铁丝镀锌铁丝	kg	5.57							5.986		33.34
2003025	钢模板各类定型大块钢模板	t	5247.26							0.051		267.91
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	6.64							4.667		30.99
2009013	螺栓混合规格	kg	5.64							6.158		34.73
2009028	铁件铁件	kg	5.65							3.626		20.49
3005004	水	m3	3.84							12.504		48.02
5503005	中(粗)砂混凝土、砂浆用堆方	m3	150							4.889		733.36
5505013	碎石(4cm)最大粒径4cm堆方	m3	145							8.928		1294.54
5509002	42.5级水泥	t	450							3.773		1697.89
7801001	其他材料费	元	1							89.82		89.82
8005005	出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92							0.213		67.79
8007046	装载机质量1.0t以内机动翻斗车F10A	台班	206.5							0.312		64.53
8009030	提升质量25t以内汽车式起重机制QY25	台班	1342.51							0.688		923.27
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	138.92							0.67		113.14
8099001	小型机具使用费	元	1							51.227		51.23
9999001	定额基价	元	1							14337		14337

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥

分项目编号: QL0202

工程名称: 现浇C30砼台帽及侧墙

单位: m3

数量: 10.42

单价: 1999.47

第 22 页共 53 页

21-2表

代 号	工 程 项 目		单 位		单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	合 计	
	工 程 细 目														
	定 额 单 位														
	工 程 数 量														
	定 额 表 号														
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	数量	金额(元)		
	直接费	元													16344.22
	措施费	I													19
		II													133.96
	企业管理费		元												456.6
	规费		元												1051.33
	利润		元												1109.05
	税金		元												1720.28
	金额合计		元												20834.44

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 分项编号: QL0203
 工程名称: 现浇C30防撞块及支座垫石
 单位: m³
 数量: 0.5
 单价: 3704.24
 第 23 页共 53 页
 21-2表

代 号	工 程 项 目		支 座 垫 石				支 座 垫 石				混 凝 土 运 输				混 凝 土 搅 拌 机 拌 和			
	工 程 细 目		板 式 支 座 垫 石 混 凝 土	现 场 加 工 支 座 垫 石 钢 筋			装 载 质 量 1t 以 内 机 动 翻 斗 车 运 混 凝 土 第 一 个 100m					容 量 750L 以 内 混 凝 土 搅 拌 机 拌 和						
号	定 额 单 位		10m3实 体	1t			100m3					10m3						
	工 程 数 量		0.05	0.2296			0.0051					0.051						
	定 额 表 号		4~6~2~87改				4~11~11~20				4~11~11~4							
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
	1001001	人 工	工日	101.25	22.8	1.14	115.43	5.5	1.263	127.86				1	0.051	5.16		
2001002	HRB400钢筋	t	3726.76				1.03	0.235	877.06									
2001022	20~22号铁丝镀锌铁丝	kg	5.57				6.9	1.584	8.82									
2003025	钢模板各类定型大块钢模板	t	5247.26	C.11	0.006	28.86												
2009013	螺栓混合规格	kg	5.64	2.7	0.135	0.76												
2009028	铁件铁件	kg	5.65	5.02	0.451	2.55												
3005004	水	m3	3.84	12	0.6	2.3												
5503005	中(粗)砂混凝土、砂浆用	m3	150	4.69	0.235	35.19												
5505013	碎石(4cm)最大粒径4cm堆	m3	145	5.57	0.428	62.12												
5509002	42.5级水泥	t	450	5.62	0.181	81.47												
7801001	其他材料费	元	1	8.8	0.44	0.44												
8005005	出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92										0.2	0.01	3.25			
8007046	装载机质量1.0t以内机动翻斗车F10A	台班	206.5									2.94	0.015	3.1				
8009030	提升质量25t以内汽车式起重机械QY25	台班	1342.51	1.48	0.074	99.35												
8099001	小型机具使用费	元	1	6.2	0.31	0.31	17.3	3.972	3.97									
9999001	定额基价	元	1	7312	381	381	3964	910	910	625	3	3	175	9	9			
-																		

编制: 吴明兰(西林县财政投资评审中心) 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇C30砼挡块及支座垫石		单位: m3		数量: 0.5		单价:		370元.24		第 24 页共 53 页		21-2表			
分项编号: QL0203																	
代 号	工 程 项 目		支座垫石			支座垫石			现场加工支座垫石钢筋			混凝土运输			混凝土搅拌机拌和		
	工 程 细 目		板式支座垫石混凝土			10m3实体			1t			装载质量1t以内机动翻斗车运混凝土 第一个100m			容量750L以内混凝土搅拌机拌和		
	定 额 单 位		10m3实体			0.05			0.2296			100m3			10m3		
	工 程 数 量		0.05			0.2296			0.0051			0.0051			0.051		
	定 额 表 号		4~6~2~87改			4~6~2~88			4~11~11~20			4~11~11~20			4~11~11~4		
工、料、机名称		单立	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)		
直接费		元				428.78			1017.71			3.1			8.42		
措施费		I	元	221.83	0.742%	1.65	138.18			3.19	0.959%	0.03	8.95	0.622%	0.06		
		II	元	380.61	1.537%	5.85	910.12	0.564%	5.13	3.19	0.154%		8.95	1.201%	0.11		
企业管理费		元		380.61	4.726%	17.99	910.12	2.242%	20.4	3.19	1.374%	0.04	8.95	3.587%	0.32		
规费		元		130.41	33.5%	43.69	127.86	33.5%	42.83	1.52	33.5%	0.51	6.2	33.5%	2.08		
利润		元		406.09	7.42%	30.13	935.66	7.42%	69.43	3.27	7.42%	0.24	9.43	7.42%	0.7		
税金		元		528.08	9%	47.53	1155.51	9%	104	3.93	9%	0.35	11.68	9%	1.05		
金额合计		元				575.6			1259.5			4.28			12.73		

编制: 吴明兰 (西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: KO+014.5勒德桥														工程名称: 现浇C30防撞块及支座垫石														单位: m3				数量: 0.5				单价: 3704.24				第 25 页共 53 页				21-2表																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
分项编号: QL0203																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
代 号														工 程 项 目																																																																						合 计																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
														工 程 细 目																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
														定 额 单 位																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
														工 程 数 量																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
														定 额 表 号																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									
														工、料、机名称														单位														单价(元)														定额														数量														金额(元)														定额														数量														金额(元)														数量														金额(元)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
1001001														人工														工日														101.25																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 现浇C30砼挡块及支座垫石			单位: m3			数量: 0.5			单价: 3704.24			第 26 页共 53 页			21-2表		
代 号	工 程 项 目															合 计				
	工 程 细 目																			
	定 额 单 位																			
	工 程 数 量																			
	定 额 表 号																			
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)						
	直接费		元												1458					
	措施费	I	元												1.73					
		II	元												11.1					
	企业管理费		元												38.76					
	规费		元												89.11					
	利润		元												100.5					
	税金		元												152.93					
	金额合计		元												1852.12					

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

工程名称: 现浇钢筋混凝土矩形板										单位: m3		数量: 30.4		单价: 2417.89		第 28 页共 53 页		21-2表	
工程名称: 现浇钢筋混凝土矩形板										单位: m3		数量: 30.4		单价: 2417.89		第 28 页共 53 页		21-2表	
代 号	工 程 项 目		现浇板上部构造				安 装		现浇板上部构造				混凝土运输						
	工 程 细 目		现浇混凝土矩形板上部构造				现浇刚架拱接头混凝土				现场加工现浇矩形板上部构造钢筋				装载质量1t以内机动翻斗车运混凝土 第一个100m				
	定 额 单 位		10m3实体				10m3实体				1t				100m3				
	工 程 数 量		3.04				0.1				8.9853				0.3101				
	定 额 表 号		4~6~8~1改				4~7~22~10改				4~6~8~4改				4~11~11~20				
号	工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)			
	人工		工日	101.25	11	33.44	3385.8	36.9	3.69	373.61	4.1	36.84	3730.02						
	HPB300钢筋		t	3708.93		0.003	11.28												
	HRB400钢筋		t	3725.76							1.03	9.21	34323.21						
	20~22号铁丝镀锌铁丝		kg	5.57							2.32	20.846	116.11						
	型钢工字钢,角钢		t	3783.18		0.012	46												
	钢管无缝钢管		t	43C1.22		0.009	39.23												
	钢模板各类定型大块钢模板		t	5247.26	0.09	0.268	1403.75												
	电焊条结422(502、506、507)3.2/4.0/5.0		kg	6.64							0.74	6.649	44.15						
	铁件铁件		kg	5.65	0.4	1.216	6.87	12.7	1.27	7.18									
	铁钉混合规格		kg	5.65				3.9	0.39	2.2									
	水		m3	3.84	15	45.6	175.1	15	1.5	5.76									
	锯材中板 δ =19~35mm, 中方混合规格		m3	10<7.93				0.55	0.055	57.64									
	油毛毡400g, 0.915m×21.95m		m2	3.5	7	21.28	74.48												
	中(粗)砂混凝土、砂浆用堆方		m3	150	4.49	13.644	2046.53	4.69	0.469	70.38									
	碎石(2cm)最大粒径2cm堆方		m3	145				8.06	0.806	116.84									
	碎石(4cm)最大粒径4cm堆方		m3	145		8.47	25.737	3731.81											
32.5级水泥		t	430				4.14	0.414	178.06										
42.5级水泥		t	450		4.23	12.868	5790.74												
其他材料费		元	1		67.9	206.416	22.1	2.21	2.21										

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 台背回填			单位: m3			数量: 135			单价: 57.95			第 27 页共 53 页			21-2表		
分项编号: QL0204																				
代 号	工 程 项 目		锥坡、拱上、台背处理												合 计					
	工 程 细 目		台背碎石土回填																	
	定 额 单 位		100m3																	
	工 程 数 量		1.35																	
	定 额 表 号		借桂2020养预4~4~3~8改																	
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)		
1001001	人工	工日	101.25	1.3	1.755	177.69									1.755			177.69		
5501005	碎石土天然堆方	m3	32.04	122.4	165.24	5294.29									165.24			5294.29		
8001002	功率75kW以内履带式推土机TY100	台班	866.45	0.11	0.149	128.67									0.149			128.67		
8001030	斗容量2.0m3履带式单斗挖掘机WY200A液压	台班	1478.3	0.11	0.149	219.53									0.149			219.53		
8001058	功率120kW以内平地机F155	台班	1168.27	0.12	0.162	189.26									0.162			189.26		
8001081	机械自身质量12~15t光轮压路机3Y-12/15	台班	576.46	0.22	0.297	171.21									0.297			171.21		
8001095	蛙式夯土机(200~620N·m)HW-280	台班	27.8	0.34	0.459	12.76									0.459			12.76		
8007041	容量6000L以内洒水汽车YG1510ZGSSEQ	台班	717.03	0.18	0.243	174.24									0.243			174.24		
9999001	定额基价	元	1	4670	6304	6304									6304			6304		
	直接费	元				6367.65												6367.65		
	措施费	I		1091.01	0.939%	10.24												10.25		
		II		6304.33	0.521%	32.85												32.85		
	企业管理费	元		6304.34	2.747%	173.18												173.18		
	规费	元		325.32	33.5%	108.98												108.98		
	利润	元		6520.61	7.42%	483.83												483.83		
	税金	元		7176.72	9%	645.91												645.91		
	金额合计	元				7822.63												7822.63		

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: KO+014.5勒德桥
 分项目编号: QL0301
 工程名称: 现浇钢筋混凝土矩形板
 单位: m3
 数量: 30.4
 单价: 2417.89
 第 29 页共 53 页
 21-2表

代

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 现浇钢筋混凝土矩形板		单位: m3		数量: 30.4		单价: 2417.89		第 31 页共 53 页		21-2表
代 号	工 程 项 目		混凝土搅拌机拌和									
	工 程 细 目		容量750L以内混凝土搅拌机拌和									
	定 额 单 位		10m3									
	工 程 数 量		3.1008									
	定 额 表 号		4~11~11~4									
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	合 计
800E005	出料容量750L以内强制式混凝土搅拌机JS750	台班	318.92	0.2	0.62	197.78				0.62	197.78	
800E046	装载质量1.0t以内机动翻斗车F10A	台班	206.5									188.25
800E027	提升质量12t以内汽车式起重机械QY12	台班	835.14									583.93
800E030	提升质量25t以内汽车式起重机械QY25	台班	1342.51									1061.12
801E028	容量32kV·A以内交流电弧焊机BX1-330	台班	168.92									197.31
809E001	小型机具使用费	元	1									151.77
999E001	定额基价	元	1	175	544	544				51104	51104	51104
	直接费	元				511.74						58639.52
	措施费	I		543.9	0.622%	3.38						47.14
		II		543.9	1.201%	6.53						447.24
	企业管理费	元		543.9	3.587%	19.51						1550.52
	规费	元		376.75	33.5%	126.21						2806.77
	利润	元		573.33	7.42%	42.54						3943.62
	税金	元		709.91	9%	63.89						6069.13
	金额合计	元				773.81						73503.94

表A.0.3-2 分项工程预算表

工程名称: 现浇C40防水混凝土铺装												单位: m3	数量: 11.9	单价:	1719.4	第 32 页共 53 页	21-2表
代 号	工 程 项 目		行车道铺装混凝土			行车道铺装钢筋			防水层			混凝土运输					
	工 程 细 目		桥面行车道铺装防水混凝土面层非泵送			桥面行车道铺装水泥及防水混凝土钢筋(直径8mm以上)			桥面防水剂(防水层)			装载质量1t以内机动翻斗车运混凝土第一个100m					
	定 额 单 位		10m3	1t					1000m2			100m3					
	工 程 数 量		1.19	1.2311					0.1263			0.1214					
	定 额 表 号		4~6~13~5改			4~6~13~8改			4~11~4~6			4~11~11~20					
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)		
1001001	人工	工日	131.25	13.3	15.827	1602.48	7.1	8.741	885.01	2.6	0.328	33.25					
2001002	HRB400钢筋	t	3726.76				1.03	1.262	4702.71								
2001022	20~22号铁丝镀锌铁丝	kg	5.57				2.55	3.139	17.49								
2003004	型钢工字钢,角钢	t	3733.18		0.002	9											
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	6.64				5.41	6.66	44.22								
3005004	水	m3	3.84	15	17.85	68.54											
5009005	桥面防水涂料聚合物渗透水性桥面防水涂料	kg	5.04							1664	210.163	3160.85					
5503005	中(粗)砂混凝土、砂浆用堆方	m3	150	4.69	5.583	837.52											
5505013	碎石(4cm)最大粒径4cm堆方	m3	145	8.26	9.832	1425.61											
5509002	42.5级水泥	t	450	4.43	5.268	2370.66											
7501001	其他材料费	元	1	228.9	272.391	272.39											
8003038	容量4000L以内沥青洒布车LS-3500	台班	606.84							0.06	0.008	4.6					
8003085	电动混凝土切缝机(含锯片摊销费用)SLF	台班	202.97	0.75	0.893	181.15											
8007046	装载质量1.0t以内机动翻斗车F10A	台班	206.5	0.45	0.536	110.58						2.94	0.357	73.69			
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	138.92				0.94	1.157	195.48								
8099001	小型机具使用费	元	1	21.8	25.942	25.94	18	22.16	22.16								
9999001	定额基价	元	1	4716	5612	5612	4318	5316	5316	17384	2196	2196	625	76	76		
-				-					-				-				

复核: 陈华生

编制: 吴明兰(西林县财政投资评审中心)

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 分项编号: QL0402
 工程名称: 现浇C40防水混凝土铺装
 单位: m3
 数量: 11.9
 单价: 1719.4
 第 33 页共 53 页
 21-2表

工 程 项 目		行车道铺装混凝土				行车道铺装钢筋				防水层				混凝土运输			
工 程 细 目		桥面行车道铺装防水混凝土面层非泵送				桥面行车道铺装水泥及防水混凝土钢筋(直径8mm以上)				桥面防水剂(防水层)				装载质量1t以内机动翻斗车运混凝土第一个100m			
定 额 单 位		10m3				1t				100m2				100m3			
工 程 数 量		1.19				1.2311				0.1263				0.1214			
定 额 表 号		4~6~13~5改				4~6~13~8改				4~11~4~6				4~11~11~20			
工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)			
直接费		元			6903.89						5867.07			3198.7			73.7
	I	元		2005.62	0.94%	18.89	1164.33			39.35	0.742%	0.29	75.91	0.959%	0.73		
措施费	II	元		5612.5	0.818%	45.91	5315.93	0.564%	29.98	2195.63	1.537%	33.75	75.91	0.154%	0.12		
		元		5612.5	2.427%	136.22	5315.93	2.242%	119.18	2195.63	4.726%	103.77	75.92	1.374%	1.04		
企业管理费		元		1747.07	33.5%	585.27	1002.18	33.5%	335.73	34.01	33.5%	11.4	36.14	33.5%	12.11		
规费		元		5815.52	7.42%	431.36	5465.09	7.42%	405.51	2333.44	7.42%	173.14	77.82	7.42%	5.77		
利润		元		8121.53	9%	730.94	6757.48	9%	608.17	3521.04	9%	316.89	93.47	9%	8.41		
税金		元															
金额合计		元			8852.47				7365.65			3837.94					101.88

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

代 号	工 程 项 目		混凝土搅拌机拌和												合 计			
	工 程 细 目	单 位	工、料、机名称	单 位	单 价 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额
1001001	人工	工日			101.25	1	1.214	122.9								26.11	2643.64	
2001002	HRB400钢筋	t			3726.76											1.262	4702.71	
2001022	20~22号铁丝镀锌铁丝	kg			5.57											3.139	17.49	
2003004	型钢工字钢,角钢	t			3783.18											0.002	9	
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg			6.64											6.66	44.22	
3005004	水	m³			3.84											17.85	68.54	
5009005	桥面防水涂料聚合物渗透水性桥面防水涂料	kg			15.04											210.163	3160.85	
5503005	中(粗)砂混凝土、砂浆用堆方	m³			150											5.583	837.52	
5505013	碎石(4cm)最大粒径4cm堆方	m³			145											9.832	1425.61	
5509002	42.5级水泥	t			450											5.268	2370.55	
7801001	其他材料费	元			1											272.391	272.39	
8003038	容量4000L以内沥青洒布车LS-3500	台班			606.84											0.008	4.6	
8003085	电动混凝土切割机(含锯片摊销费)SLF	台班			202.97											0.893	181.15	
8005005	出料容量750L以内强制式混凝土搅拌机JS750	台班			318.92	0.2	0.243	77.42								0.243	77.42	
8007046	装载机质量1.0t以内机动翻斗车F10A	台班			206.5											0.892	184.27	
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班			168.92											1.157	195.48	
8099001	小型机具使用费	元			1											48.102	48.1	
9999001	定额基价	元			1	175	213	213								13413	13413	

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 桥面连续			单位: t			数量: 0.431			单价: 532.46			第 36 页共 53 页			21-2表		
分项编号: QL0404																				
代 号	工 程 项 目		现浇板上部构造												合 计					
	工 程 细 目		现场加工现浇连续板上部构造钢筋																	
	定 额 单 位		1t																	
	工 程 数 量		0.431																	
	定 额 表 号		4~6~8~5改																	
1001001	人 工	工 日	101.25	5	2.155	218.19										2.155	218.19			
2001002	HRB400钢筋	t	3725.76	1.03	0.442	1646.39										0.442	1646.39			
2001022	20~22号铁丝镀锌铁丝	kg	5.57	2.6	1.121	6.24										1.121	6.24			
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	5.64	2.55	1.099	7.3										1.099	7.3			
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	163.92	0.37	0.159	26.94										0.159	26.94			
8099001	小型机具使用费	元	1	13.4	5.775	5.78										5.775	5.78			
9999001	定额基价	元	1	3969	1711	1711										1711	1711			
		直接费	元				1910.84										1910.84			
		措施费	I	元		264.19														
			II	元		1710.68	0.564%	9.65									9.65			
		企业管理费	元		1710.68	2.242%	38.35										38.35			
		规费	元		234.34	33.5%	78.5										78.5			
		利润	元		1758.68	7.42%	130.49										130.49			
		税金	元		2167.83	9%	195.11										195.11			
		金额合计	元				2362.94										2362.94			

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥										第 37 页共 53 页										21-2表									
分项编号: QL050104										工程名称: 板式橡胶支座										数量: 11.618 单价: 174.41									
										单位: dm3																			
代 号	工 程 项 目			普通钢支座及板式橡胶支座																								合 计	
	工 程 细 目			安装四氟板式橡胶组合支座																									
	定 额 单 位			1dm3																									
	工 程 数 量			11.618																									
	定 额 表 号			4~7~27~4																									
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)									
1001001	人工	工日	101.25	0.1	1.162	117.63									1.162				1.162	117.63									
2001002	HRB400钢筋	t	3726.76		0.012	43.3									0.012				0.012	43.3									
2003005	钢板Q235, δ=5~40mm	t	5720	0.01	0.128	731									0.128				0.128	731									
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	6.64	0.1	1.162	7.71									1.162				1.162	7.71									
6001002	四氟板式橡胶组合支座GJZF4系列、GYZF4系列	dm3	59.83	1	11.618	695.1									11.618				11.618	695.1									
7801001	其他材料费	元	1	2.6	30.207	30.21									30.207				30.207	30.21									
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	168.92	0.02	0.232	39.25									0.232				0.232	39.25									
8099001	小型机具使用费	元	1	0.2	2.324	2.32									2.324				2.324	2.32									
9999001	定额基价	元	1	120	1392	1392									1392				1392	1392									
	直接费	元				1666.53														1666.53									
	措施费	I		168.61																									
		II		1391.61	0.564%	7.85														7.85									
	企业管理费		元		1391.61	2.242%	31.2													31.2									
	规费		元		141.16	33.5%	47.29													47.29									
	利润		元		1430.66	7.42%	106.16													106.16									
	税金		元		1859.02	9%	167.31													167.31									
	金额合计		元				2026.34													2026.34									

编制: 吴明兰 (西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥													21-2表									
分项目编号: QL0502C2													工程名称: 沥青麻絮伸缩缝		单位: m		数量: 5.5		单价: 340元.31		第 38 页共 53 页	
代 号	工 程 项 目		模数式伸缩缝				模数式伸缩缝				模数式伸缩缝				模数式伸缩缝				合 计			
	工 程 细 目		模数式伸缩缝(伸缩量480mm以内)				模数式伸缩缝预留槽混凝土				模数式伸缩缝预留槽钢筋											
	定 额 单 位		1m				10m3				1t											
	工 程 数 量		5.5				0.05				0.1382											
	定 额 表 号		4~11~7~1				4~11~7~5改				4~11~7~6											
	工、料、机名称	单 位	单 价 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	定 额	数 量	金 额 (元)	数 量	金 额 (元)					
1001001	人工	工日	101.25	0.9	4.95	501.19	24.7	1.235	125.04	9.5	1.313	132.93	7.498		759.16							
2001001	HPB300钢筋	t	3708.93							0.16	0.022	79.96	0.022		79.96							
2001002	HRB400钢筋	t	3726.76							0.87	0.12	447.57	0.12		447.57							
2001019	钢丝绳股6-7×19, 绳径7.1~9mm; 股丝6×37, 绳径14.1~15.5mm	t	6000		0.011	66							0.011		66							
2001020	钢绞线扁丝切断型、钢丝切断型、高强度销型、剪切波纹型、剪切压痕型	t	6000				0.05	0.003	15.9				0.003		15.9							
2001022	20~22号铁丝镀锌铁丝	kg	5.57							4.1	0.567	3.16	0.567		3.16							
2009011	电焊条结422(502、506、507、3.2/4.0/5.0	kg	6.64	0.66	3.63	24.1				4.3	0.594	3.95	4.224		28.05							
3005004	水	m3	3.84				15	0.75	2.88				0.75		2.88							
4003002	锯材中板 δ =19~35mm, 中方混合规格	m3	1047.93				0.02	0.001	1.05				0.001		1.05							
5503005	中(粗)砂混凝土、砂浆用堆方	m3	150				4.49	0.224	33.66				0.224		33.66							
5505013	碎石 (4cm) 最大粒径4cm堆方	m3	145				8.47	0.423	61.38				0.423		61.38							
5509002	42.5级水泥	t	450				4.23	0.212	95.24				0.212		95.24							
6003004	模数式伸缩装置240型	m	2393.16	1	5.5	13162.38							5.5		13162.38							
7801001	其他材料费	元	1	20.8	114.4	114.4	1.9	0.095	0.1				114.495		114.5							
8009027	提升质量12t以内汽车式起重机械Q12	台班	835.14	0.04	0.22	183.73	0.42	0.021	17.54				0.241		201.27							
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	168.92	0.14	0.77	130.07				0.84	0.116	19.61	0.886		149.68							
8099001	小型机具使用费	元	1	11.4	62.7	62.7	3.8	0.19	0.19	19.4	2.681	2.68	65.571		65.57							
编制: 吴明兰(西乡县财政投资评审中心)													复核: 陈华生									

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 沥青麻絮伸缩缝		单位: m	数量: 5.5	单价: 3406.31	第 39 页共 53 页		21-2表
代 号	工 程 项 目	模数式伸缩缝			模数式伸缩缝			模数式伸缩缝	
	工 程 细 目	模数式伸缩缝(伸缩量480mm以内)			模数式伸缩缝预留槽混凝土			模数式伸缩缝预留槽钢筋	
	定 额 单 位	1m			10m3			1t	
	工 程 数 量	5.5			0.05			0.1382	
	定 额 表 号	4~11~7~1			4~11~7~5改			4~11~7~6	
9909001	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)
	定额基价	元	1	2596	14280	14280	6009	300	300
	直接费	元				14244.57			352.98
		I		917.25			149.26	0.742%	1.11
	措施费	元		14280.5	0.564%	80.54	300.46	1.537%	4.62
		II		14280.5	2.242%	320.17	300.46	4.726%	14.2
	企业管理费	元		623.7	33.5%	208.94	129.3	33.5%	43.31
	规费	元		14681.21	7.42%	1089.35	320.38	7.42%	23.77
	利润	元		15943.57	9%	1434.92	439.99	9%	39.6
	税金	元							479.59
	金额合计	元				17378.49			876.61
									15287.4
									1.11
									88.72
									348.53
									300.72
									1161.3
									1546.9
									18734.68

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥														工程名称: 现浇C30混凝土防撞护栏														单位: m														数量: 46.08														单价: 727.66														第 40 页共 53 页														21-2表																																																																																			
代 号														工 程 项 目														现浇钢筋混凝土防撞护栏														现浇钢筋混凝土防撞护栏														合 计																																																																																																															
														工 程 细 目														现浇钢筋混凝土防撞护栏墙体混凝土														现浇钢筋混凝土防撞护栏墙体钢筋																																																																																																																													
														定 额 单 位														10m3实体														1t																																																																																																																													
														工 程 数 量														1.88														3.0736																																																																																																																													
														定 额 表 号														5~1~1~5改														5~1~1~6改																																																																																																																													
														工、料、机名称														单位														单价(元)														定额														数量														金额(元)														定额														数量														金额(元)																																									
1001001														人工														工日														111.25														16														30.08														3045.6														8.8														27.048														2738.58														57.128														5784.18													
2001001														HPB300钢筋														t														3718.93																												0.002														6.97																																										0.002														6.97																											
2001002														HRB400钢筋														t														3716.76																																										1.03														3.15														11740.93														3.15														11740.93																											
2001022														20~22号铁丝镀锌铁丝														kg														5.57																																										5.1														15.675														87.31														15.675														87.31																											
2003025														钢模板各类定型大块钢模板														t														5217.26														0.1														0.19														996.35																																										0.19														996.35																											
2009028														铁件铁件														kg														5.65														13.3														25.004														141.27																																										25.004														141.27																											
3005004														水														m3														3.84														12														22.56														86.63																																										22.56														86.63																											
4003001														原木混合规格														m3														819.57														0.04														0.081														71.91																																										0.081														71.91																											
4003002														锯材中板 5=19~35mm, 中方混合规格														m3														1017.93														0.06														0.115														120.18																																										0.115														120.18																											
5503005														中(粗)砂混凝土、砂浆用堆方														m3														150														4.69														8.821														1323.14																																										8.821														1323.14																											
5505013														碎石(4cm)最大粒径4cm堆方														m3														145														8.57														16.108														2335.64																																										16.108														2335.64																											
5509002														42.5级水泥														t														450														3.62														6.807														3063.37																																										6.807														3063.37																											
7801001														其他材料费														元														1														14.2														26.696														26.7																																										26.696														26.7																											
8005002														出料容量250L以内强制式混凝土搅拌机JD250														台班														116.33														0.29														0.545														90.68																																										0.545														90.68																											
8007046														装载质量1.0t以内机动翻斗车F10A														台班														206.5														0.28														0.526														108.7																																										0.526														108.7																											
8099001														小型机具使用费														元														1														4.8														9.024														9.02														32.888														32.89														41.912														41.91																											
9999001														定额基价														元														1														5099														9586														9586														4299														13215														13215														22800														22800													
-																																																								-																																																																						-																																									

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 现浇C30混凝土防撞护栏			单位: m			数量: 46.08			单价: 727.66			第 41 页共 53 页			21-2表		
代 号	工 程 项 目		现浇钢筋混凝土防撞护栏			现浇钢筋混凝土防撞护栏			现浇钢筋混凝土防撞护栏						合 计					
	工 程 细 目		现浇钢筋混凝土防撞护栏墙体混凝土			现浇钢筋混凝土防撞护栏墙体混凝土			现浇钢筋混凝土防撞护栏墙体钢筋											
	定 额 单 位		10m3实体			10m3实体			1t											
	工 程 数 量		1.88			1.88			3.0736											
	定 额 表 号		5~1~1~5改			5~1~1~5改			5~1~1~6改											
	工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)					
	直接费		元				11426.17			14599.71					26025.88					
	措施费	I	元			3414.87	0.742%	25.34	2907.51						25.34					
		II	元			9585.7	1.537%	147.33	13214.79	0.564%	74.53				221.86					
	企业管理费		元			9585.7	4.726%	453.02	13214.79	2.242%	296.28				749.3					
	规费		元			3154.1	33.5%	1056.62	2738.58	33.5%	917.42				1974.05					
	利润		元			10211.39	7.42%	757.69	13585.59	7.42%	1008.05				1765.74					
	税金		元			13866.17	9%	1247.96	16895.99	9%	1520.64				2768.59					
	金额合计		元				15114.12			18416.63					33530.75					

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勤德桥		工程名称: 现浇C30砼搭板桩梁		单位: m3	数量: 15.8	单价: 14=7.93	第 43 页共 53 页		21-2表
代 号	工 程 项 目	现浇混凝土桥头搭板		现浇混凝土桥头搭板		混凝土运输		混凝土搅拌机拌和	
	工 程 细 目	混凝土搭板		现场加工桥头搭板钢筋		装载质量1t以内机动翻斗车运混凝土 第一个100m		容量750L以内混凝土搅拌机拌和	
	定 额 单 位	10m3实体		1t		100m3		10m3	
	工 程 数 量	1.58		2.0018		0.1612		1.6116	
	定 额 表 号	4~6~14~1改		4~6~14~3		4~11~11~20		4~11~11~4	
990001	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)
	定额基价	元	1	4188	6617	6617	4074	8156	8156
	直接费	元				8248.07			9071.65
	措施费	元		2541.88	0.742%	18.86	1466.99		
	企业管理费	元		6616.78	1.537%	101.7	8155.58	0.564%	46
	规费	元		6616.78	4.726%	312.71	8155.58	2.242%	182.85
	利润	元		7050.05	7.42%	523.11	8384.42	7.42%	622.12
	税金	元		9984.27	9%	898.58	10365.99	9%	932.94
	金额合计	元				10882.85			11298.93
									135.28
									97.87
									282.68
									0.622%
									282.68
									1.201%
									3.4
									282.68
									3.587%
									10.14
									16.08
									33.5%
									7.67
									7.42%
									297.98
									9%
									368.97
									33.21
									402.18

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 分项编号: QL0504
 工程名称: 现浇C30砼搭板板梁
 单位: m3
 数量: 15.8
 单价: 1437.93
 第 44 页共 53 页
 21-2表

代 号	工 程 项 目		工 程 细 目		定 额 单 位		工 程 数 量		定 额 表 号		合 计									
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	定额	数量	金额(元)	数量	金额(元)	数量	金额(元)	数量	金额(元)	数量
1001001	人工	工日	101.25																	
2001002	HRB400钢筋	t	3726.76																	
2001022	20~22号铁丝镀锌铁丝	kg	5.57																	
2003004	型钢工字钢,角钢	t	3733.18																	
2003026	组合钢模板	t	4736.68																	
2009011	电焊条结422(502、506、507)3.2/4.0/5.0	kg	6.64																	
2009028	铁件铁件	kg	5.65																	
3005004	水	m3	3.84																	
4003001	原木混合规格	m3	889.57																	
4003002	锯材中板 δ = 19~35mm, 中方混合规格	m3	1047.93																	
5503005	中(粗)砂混凝土、砂浆用堆方	m3	150																	
5505013	碎石(4cm)最大粒径4cm堆方	m3	145																	
5509002	42.5级水泥	t	450																	
7801001	其他材料费	元	1																	
8005005	出料容量750L以内强制式混凝土搅拌机IS750	台班	318.92																	
8007046	装载机质量1.0t以内机动翻斗车F10A	台班	206.5																	
8015028	容量32kV·A以内交流电弧焊机BX1-330	台班	168.92																	
8099001	小型机具使用费	元	1																	

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥										工程名称: 现浇C30砼搭板枕梁										单位: m3			数量: 15.8			单价: 1437.93			第 45 页共 53 页			21-2表									
代 号		工 程 项 目																														合 计									
		工 程 细 目																																							
		定 额 单 位																																							
		工 程 数 量																																							
		定 额 表 号																																							
		工、料、机名称					单位		单价(元)			定额		数量		金额(元)			定额		数量		金额(元)			数量		金额(元)													
9999001		定额基价					元		1														15156			15156															
		直接费					元																17683.55			17683.55															
		措施费					I		元														21.59			21.59															
							II		元												151.25			151.25																	
		企业管理费					元																507.08			507.08															
		规费					元																1304.86			1304.86															
		利润					元																1175.01			1175.01															
		税金					元																1875.9			1875.9															
		金额合计					元																22719.24			22719.24															

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥		工程名称: 锥坡非水及防护		单位: m3		数量: 50.5		单价:		462.35		第 46 页共 53 页		21-2表	
分项编号: QL0505															
代 号	工 程 项 目		浆砌片石			基础垫层			锥坡填土、拱上填料、台背排水			石砌护坡			
	工 程 细 目		浆砌片石基础、护底、截水墙			基础垫层填砂砾(砂)			锥坡填土			浆砌片石护坡(坡高10m以内)			
	定 额 单 位		10m3			10m3实体			10m3实体			10m3实体			
	工 程 数 量		2.2			0.95			4			1.9			
	定 额 表 号		4~5~2~1改			4~11~5~1改			4~11~2~1			1~4~11~2改			
工、料、机名称		单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)
1001001	人工	工日	101.25	6.6	14.52	1470.15	2.9	2.755	278.94	4.3	17.2	1741.5	7.7	14.63	1481.29
3005004	水	m³	3.84	4	8.8	33.79							16	30.4	116.74
5503004	砂路面用堆方	m³	160				12.75	12.113	1938						
5503005	中(粗)砂混凝土、砂浆用堆方	m³	150	3.82	8.404	1260.6							4.06	7.714	1157.1
5505005	片石码方	m³	135	11.5	25.3	3415.5							11.5	21.85	2949.75
5509002	42.5级水泥	t	450	0.93	2.048	921.69							1	1.906	857.57
7801001	其他材料费	元	1	1.2	2.64	2.64							3.5	6.65	6.65
8001045	斗容量1.0m3轮胎式装载机ZL20	台班	573.85	0.08	0.176	101							0.1	0.19	109.03
8005010	出料容量400L以内灰浆搅拌机UJ325	台班	130.18	0.15	0.33	42.96							0.15	0.285	37.1
9999001	定额基价	元	1	2183	4802	4802	1299	1234	1234	457	1828	1828	2394	4548	4548
	直接费	元				7248.33			2216.94			1741.5			6715.22
	措施费	I		1691.66	0.742%	12.55	292.8	0.742%	2.17	1828.02	0.742%	13.56	1705.34	0.742%	12.65
		II		4802.01	1.537%	73.81	1233.58	1.537%	18.96	1828.02	1.537%	28.1	4548.06	1.537%	69.9
	企业管理费	元		4802.01	4.726%	226.94	1233.58	4.726%	58.3	1828.02	4.726%	86.39	4548.06	4.726%	214.94
	规费	元		1521.38	33.5%	509.66	278.94	33.5%	93.45	1741.5	33.5%	583.4	1529.38	33.5%	512.34
	利润	元		5115.31	7.42%	379.56	1313.01	7.42%	97.43	1956.06	7.42%	145.14	4845.57	7.42%	359.54
	税金	元		8450.86	9%	760.58	2487.24	9%	223.85	2598.1	9%	233.83	7884.6	9%	709.61
	金额合计	元				9211.43			2711.1			2831.93			8594.22

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: 台后排水			单位: m3			数量: 32.4			单价: 211.8			第 48 页共 53 页			21-2表		
代 号	工 程 项 目		锥坡填土、拱上填料、台背排水												合 计					
	工 程 细 目		台背排水																	
	定 额 单 位		10m3实体																	
	工 程 数 量		3.24																	
	定 额 表 号		4~11~2~3改																	
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)			
1001001	人工	工日	1C1.25	5.5	17.82	1804.28										17.82	1804.28			
5007001	土工布宽4~5m	m2	5.6	7.46	24.17	135.35										24.17	135.35			
5501003	黏土堆方	m3	28	4.38	14.191	397.35										14.191	397.35			
5505005	片石码方	m3	135	1.32	4.277	577.37										4.277	577.37			
5505015	碎石(8cm)最大粒径8cm堆方	m3	145	4.73	15.325	2222.15										15.325	2222.15			
8099001	小型机具使用费	元	1	4.5	14.58	14.58										14.58	14.58			
9999001	定额基价	元	1	1146	3712	3712										3712	3712			
	直接费		元			5151.09											5151.09			
	措施费	I		1908.49	0.742%	14.16											14.16			
		II		3711.57	1.537%	57.05											57.05			
	企业管理费		元	3711.57	4.726%	175.41											175.41			
	规费		元	1804.27	33.5%	604.43											604.43			
	利润		元	3958.18	7.42%	293.7											293.7			
	税金		元	6295.83	9%	566.63											566.63			
	金额合计		元			6862.46											6862.46			

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: KO+014.5勒德桥
 分项目编号: QL0602
 工程名称: 编织袋围堰 (高1.5m)
 单位: m
 数量: 42
 单价: 277.45
 第 51 页共 53 页
 21-2表

代 号	工 程 项 目		编 织 袋 围 堰												合 计			
	工 程 细 目		编织袋围堰高1.5m															
	定 额 单 位		10m围堰															
	工 程 数 量		4.2															
	定 额 表 号		4~2~2~3改															
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)				
1001001	人工	工日	101.25	11.8	49.56	5017.95						49.56	5017.95					
5001052	塑料编织袋装砂井用	个	1.2	543	2280.6	2736.72						2280.6	2736.72					
9999001	定额基价	元	1	2041	8574	8574						8574	8574					
	直接费	元				7754.67							7754.67					
	措施费	I		5267.24	0.742%	39.08							39.08					
		II		8574.11	1.537%	131.78							131.78					
	企业管理费	元		8574.11	4.726%	405.21							405.21					
	规费	元		5017.95	33.5%	1681.01							1681.01					
	利润	元		9150.19	7.42%	678.94							678.94					
	税金	元		10690.71	9%	962.16							962.16					
	金额合计	元				11652.87							11652.87					

编制: 吴明兰 (西林县财政投资评审中心)

复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥
 分项编号: QL0603
 工程名称: M7.5浆砌片石挡墙
 单位: m3
 数量: 46.2
 单价: 436.06
 第 52 页共 53 页
 21-2表

代 号	工 程 项 目		石砌挡土墙										合 计			
	工 程 细 目		浆砌片石挡土墙墙身													
	定 额 单 位		10m3实体													
	工 程 数 量		4.62													
	定 额 表 号		1~4~16~7改													
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)		
1001J01	人工	工日	101.25	6.8	31.416	3180.87						31.416	3180.87			
2001J21	8~12号铁丝镀锌铁丝	kg	5.28	2.7	12.474	65.86						12.474	65.86			
2009J30	铁钉混合规格	kg	5.65	0.1	0.462	2.61						0.462	2.61			
3005J04	水	m3	3.84	7	32.34	124.19						32.34	124.19			
4003J01	原木混合规格	m3	889.57	0.03	0.139	123.29						0.139	123.29			
4003J02	锯材中板 δ =19~35mm, 中方混合规格	m3	1047.93	0.02	0.092	96.83						0.092	96.83			
5001J13	PVC塑料管(Φ50mm) Φ50mm	m	9.73	1.8	8.316	80.91						8.316	80.91			
5501J03	黏土堆方	m3	28	0.18	0.832	23.28						0.832	23.28			
5503J05	中(粗)砂混凝土、砂浆用堆方	m3	150	3.89	17.972	2695.77						17.972	2695.77			
5505J05	片石码方	m3	135	11.5	53.13	7172.55						53.13	7172.55			
5505J15	碎石(8cm) 最大粒径8cm堆方	m3	145	0.11	0.508	73.69						0.508	73.69			
5509J02	42.5级水泥	t	450	0.95	4.403	1981.29						4.403	1981.29			
7801J01	其他材料费	元	1	3.5	16.17	16.17						16.17	16.17			
8001J45	斗容量1.0m3轮胎式装载机 ZL20	台班	573.85	0.1	0.462	265.12						0.462	265.12			
8005J10	出料容量400L以内灰浆搅拌机 JH1325	台班	130.18	0.15	0.693	90.21						0.693	90.21			
9999J01	定额基价	元	1	2344	10829	10829						10829	10829			
	-				-								-			

编制: 灵明兰 (西林县财政投资评审中心) 复核: 陈华生

表A.0.3-2 分项工程预算表

编制范围: K0+014.5勒德桥			工程名称: M7.5浆砌片石挡墙			单位: m3		数量: 46.2		单价: 36.06		第 53 页共 53 页		21-2表		
代 号	工 程 项 目		石砌挡土墙										合 计			
	工 程 细 目		浆砌片石挡土墙墙身													
	定 额 单 位		10m3实体													
	工 程 数 量		4.62													
	定 额 表 号		1~4~16~7改													
	工、料、机名称	单位	单价(元)	定额	数量	金额(元)	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)		
	直接费	元				15992.65								15992.65		
	措施费	I	元	3704.75	0.622%	23.04								23.04		
		II	元	10828.78	1.201%	130.05								130.05		
	企业管理费		元		10828.78	3.587%	388.43							388.43		
	规费		元		3297.81	33.5%	1104.77							1104.77		
	利润		元		11370.31	7.42%	843.68							843.68		
	税金		元		18482.62	9%	1663.44							1663.44		
	金额合计		元			20146.06								20146.06		

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-3 材料预算单价计算表

建设项目名称: 西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围: K0+014.5勒德桥

22表

第 1 页 共 1 页

代号	规格名称	单位	原价 (元)	供应地点	运杂费				原价运费 合计 (元)	场外运输损耗		采购及保管费		预算单价 (元)
					运输方式、比重及运距 (KM)	毛质量系数或单位毛质量	运杂费构成说明或计算式	单位运费 (元)		费率 (%)	金额 (元)	费率 (%)	金额 (元)	
2001001	HPB300钢筋	t	3640.12	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	3681.32			0.75	27.61	3708.93
2001002	HRB400钢筋	t	3657.82	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	3699.02			0.75	27.74	3726.76
2001021	8~12号铁丝	kg	5.2	西林县---工地	汽车、1.0、39.0	0.001	(0.8*39.0+10.0*1.0)*1*0.001	0.04	5.24			0.75	0.04	5.28
2001022	20~22号铁丝	kg	5.49	西林县---工地	汽车、1.0、39.0	0.001	(0.8*39.0+10.0*1.0)*1*0.001	0.04	5.53			0.75	0.04	5.57
2003004	型钢	t	3713.82	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	3755.02			0.75	28.16	3783.18
2003008	钢管	t	4228	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	4269.2			0.75	32.02	4301.22
2003025	钢模板	t	5167	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	5208.2			0.75	39.06	5247.26
2003026	组合钢模板	t	4690	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	4731.2			0.75	35.48	4766.68
2009011	电焊条	kg	6.46	西林县---工地	汽车、1.0、39.0	0.0011	(0.8*39.0+10.0*1.0)*1*0.0011	0.05	6.51			2.06	0.13	6.64
2009013	螺栓	kg	5.49	西林县---工地	汽车、1.0、39.0	0.001	(0.8*39.0+10.0*1.0)*1*0.001	0.04	5.53			2.06	0.11	5.64
2009028	铁件	kg	5.49	西林县---工地	汽车、1.0、39.0	0.0011	(0.8*39.0+10.0*1.0)*1*0.0011	0.05	5.54			2.06	0.11	5.65
2009030	铁钉	kg	5.49	西林县---工地	汽车、1.0、39.0	0.0011	(0.8*39.0+10.0*1.0)*1*0.0011	0.05	5.54			2.06	0.11	5.65
3001001	石油沥青	t	4320	西林县---工地	汽车、1.0、39.0	1	(0.8*39.0+10.0*1.0)*1	41.2	4361.2			2.06	89.84	4451.04
4003001	原木	m3	840.71	西林县---工地	汽车、1.0、39.0	0.75	(0.8*39.0+10.0*1.0)*1*0.75	30.9	871.61			2.06	17.96	889.57
4003002	锯材	m3	1000	西林县---工地	汽车、1.0、39.0	0.65	(0.8*39.0+10.0*1.0)*1*0.65	26.78	1026.78			2.06	21.15	1047.93

编制: 吴明兰(西林县财政投资评审中心)

复核: 陈华生

表A.0.3-6 施工机械台班单价计算表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

序 号	代 号	机 械 名 称	台班单 价 (元)	不变费用(元)		可变费用 (元)														车船税	合 计		
				调整系数:		机械工		重油		汽油		柴油		煤		电		水				木柴	
				定额	调整值	定额	费用	定额	费用	定额	费用	定额	费用	定额	费用	定额	费用	定额	费用			定额	费用
1	3001002	功率75kW以内履带式推土机	866.45	262.67	262.67	2	202.5					54.97	401.281									603.781	
2	3001027	斗容量1.0m³履带式单斗挖掘机	1174.46	425.12	425.12	2	202.5					74.91	546.843									749.343	
3	3001030	斗容量2.0m³履带式单斗挖掘机	1478.30	604.71	604.71	2	202.5					91.93	671.089									873.589	
4	3001035	斗容量1.0m³履带式单斗挖掘机	1033.08	358.34	358.34	2	202.5					64.69	472.237									674.737	
5	3001045	斗容量1.0m³轮胎式装载机	573.85	114.16	114.16	1	101.25					49.03	357.919								0.52	459.689	
6	3001058	功率120kW以内平地机	1168.27	365.13	365.13	2	202.5					82.13	599.549								1.09	803.139	
7	3001066	功率75kW以内履带式拖拉机	642.26	144.84	144.84	1	101.25					54.27	396.171									497.421	
8	3001080	机械自身质量10~12t光轮压路机	503.00	156.47	156.47	1	101.25					33.6	245.28									346.53	
9	3001081	机械自身质量12~15t光轮压路机	576.46	183.21	183.21	1	101.25					40	292									393.25	
10	3001083	机械自身质量18~21t光轮压路机	739.61	206.2	206.2	1	101.25					59.2	432.16									533.41	
11	3001095	蛙式夯土机(200~620N·m)	27.80	15.14	15.14											17.34	12.658					12.658	
12	3003038	容量4000L以内沥青洒布车	606.84	197.33	197.33	1	101.25			34.28	307.834										0.43	409.514	
13	3003079	混凝土电动真空吸水机组	134.92	21.57	21.57	1	101.25									16.58	12.103					113.353	
14	3003085	电动混凝土切缝机(含锯片摊销费用)	202.97	87.89	87.89	1	101.25									18.95	13.834					115.084	
		-														-						-	

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生

表A.0.3-6 施工机械台班单价计算表

建设项目名称：西林县古障镇央革村勒德屯同入平沙糖桔产业桥梁建设项目
编制范围：K0+014.5勒德桥

序 号	代 号	机 械 名 称	台班单 价 (元)	不变费用(元)		可变费用(元)												电	水		木柴		车船税	合计
				调整系数:		1.0	调整值	机械工		重油 --元/kg	汽油 8.98元/kg		柴油 7.3元/kg		煤 --元/t		0.73元/kw.h		--元/m3	--元/kg				
				定额	调整值			定额	费用		定额	费用	定额	费用	定额	费用	定额				费用			
15	8005002	出料容量250L以内 强制式混凝土搅拌 机	166.33	25.51	25.51	1	101.25								54.2	39.566						140.816		
16	8005005	出料容量750L以内 强制式混凝土搅拌 机	318.92	85.8	85.8	1	101.25								180.65	131.87 5						233.125		
17	8005010	出料容量400L以内 灰浆搅拌机	130.18	13.23	13.23	1	101.25								21.51	15.702						116.952		
18	8007014	装载质量8t以内自 卸汽车	668.83	205.99	205.99	1	101.25					49.45	360.98 5								0.6	462.835		
19	8007015	装载质量10t以内自 卸汽车	747.22	241.33	241.33	1	101.25					55.32	403.83 6								0.8	505.886		
20	8007041	容量6000L以内洒水 汽车	717.03	307.39	307.39	1	101.25				34.29	307.92 4									0.47	409.644		
21	8007043	容量10000L以内洒 水汽车	1093.2 1	605.76	605.76	1	101.25						52.8	385.44							0.76	487.45		
22	8007046	装载质量1.0t以内 机动翻斗车	206.50	39.48	39.48	1	101.25						9	65.7							0.07	167.02		
23	8009027	提升质量12t以内汽 车式起重机	835.14	408.05	408.05	2	202.5						30.59	223.30 7							1.28	427.087		
24	8009030	提升质量25t以内汽 车式起重机	1342.5 1	841.18	841.18	2	202.5						40.65	296.74 5							2.08	501.325		
25	8015013	锯片直径500mm以内 木工圆锯机	125.76	5.56	5.56	1	101.25								25.96	18.951						120.201		
26	8015028	容量32kW·A以内交 流电弧焊机	168.92	5.17	5.17	1	101.25								85.62	62.503						163.753		
27	8017049	排气量9m3/min以内 机动空气压缩机	710.65	270.17	270.17								60.34	440.48 2								440.482		
		-								-						-								

编制：吴明兰(西林县财政投资评审中心)

复核：陈华生