

## 涵洞工程数量表( 铅圆管涵 )

# 加尤镇百陇村那坤屯道路维修项目

S4-2

第1页 共1页

序号	中心桩号	结 构 类 型	交 角 (° )	孔数及孔径 (孔-m)	涵长 (m)	洞口形式		工 程 数 量(市政预制管节单位为m， 沥青麻絮及油毛毡为m <sup>2</sup> ， 其余均为m <sup>3</sup> )						备注
						进洞口	出洞口	市政预制管 节 (m)	C20(洞身 帽石)	M7.5浆砌片石 (洞身基础)	M7.5浆砌片石 (洞身垫层)	M7.5浆砌片石 (翼墙墙身)	M7.5浆砌片石 (翼墙基础)	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	AK0+300	圆管涵	90	1-φ0.6	5.1	边沟跌水井	一字墙	5.10	0.32	1.56	2.37	0.98	0.86	
2	AK0+600	圆管涵	90	1-φ0.6	5.1	边沟跌水井	一字墙	5.10	0.32	1.56	2.37	0.98	0.86	
3	BK0+800	圆管涵	90	1-φ0.6	5.1	边沟跌水井	一字墙	5.10	0.32	1.56	2.37	0.98	0.86	
合 计					15.3			15.30	0.96	4.68	7.11	2.94	2.58	

编制:

复核：