

路面工程数量表

S3-2

工程名称：凌云县伶站乡均亭村六任屯至初化村老西亭路口道路硬化建设项目

第 1 页 共 1 页

序号	起讫桩号	长度 (m)	行 车 道						路 肩			路面加宽 面积m ²	错车道 面积 面积m ²	备注
			15cm混凝土面层			10cm碎石调平层			培土路肩					
			宽度 (m)	厚度 (cm)	面积m ²	宽度 (m)	厚度 (cm)	面积m ²	宽度 (m)	厚度 (cm)	体积m ³			
1	2	3	4	5	6	10	11	12	15	16	17	18	19.00	20
1	K0+000-K2+648	2648	3.5	15	9268.00	3.5	10.0	9268.00			317.760		220.50	
	合 计	2648			9268.000			9268.000			317.760		220.500	

编制：

复核：