

# 圆管涵工程数量表

凌云县伶站乡均亭村六任屯至初化村老西亭路口道路硬化建设项目

S4-3 第 1 页 共 1 页

编号	中心桩号	交角(度)	孔数-跨径×净高 (孔-米)	涵长(米)	结构类型	进出口形式		工程数量													备注	
						进口	出口	混凝土 (m³)					M10砂浆砌片块石 (m3)	钢筋		基底填筑碎石土 (m3)	拆除既有圻工结构 (m3)	挖除20cm既有水泥路面 (m3)	台背回填砂砾石 (m³)	开挖 (m³)		
								管身(成品预制管)(C30砼)	端墙(C20砼)	管座(C20砼)	基础(C20砼)	帽石、挡块(C20砼)		洞口跌水井、铺砌沟	HPB300 (Kg)					HRB400 (Kg)		土方
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
1	K0+350	90	1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		管涵采用预制成品，新建位置现场确定
2	K0+700	90	1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
3	K0+900		1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
4	K1+300		1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
5	K1+600		1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
6	K1+900		1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
7	K2+300		1-Φ0.60	5.0	钢筋砼圆管涵	铺砌沟	铺砌沟	1.5	8	3.6		0.35	11.5	348.0		4.4			40	26		
8																						
9																						
10																						
11																						
12																						
13																						
14																						
15																						
16																						
17																						
18																						
19																						
20																						
	合计			35.0				10.5	56.0	24.9		2.5	80.6	2435.8		31.0			280.0	185.2		

编制：余翠芬

复核：李军